

- 1 All dimensions in millimetres unless otherwise stated.
- 2 Do not scale off drawing. All dimensions to be checked on site.

Specification

Drainage Insert PCC lintels over drain runs passing through external walls sized to Local Authority Building Control Officer approval and with minimum end bearings of 150mm. Drains passing under buildings to be encased in minimum 150mm concrete.

Storm Water Drainage Downpipes to discharge into PVCu back inlet gulleys connected into new soakaway located minimum 5.0m from property. Underground pipework to be 110mm PVCu bedded on (min 100mm) and encased in granular material to Building Control Officers approval. Pipework to be laid to minimum 1:40 fall

Foul Water Drainage Underground pipework to be 110mm PVCu bedded on (min 100mm) and encased in granular material to Building Control Officers approval. Pipework to be laid to minimum 1:40 fall. Inspection Chambers (generally minimum 450 x 450mm minimum internal size) to be preformed Universal Inspection Chambers or constructed with 225mm thick engineering brickwork with 150mm concrete slab base fitted with standard air tight medium duty frame and cover. Half round channels should be used in chambers with branches discharging into channel at or above the level of the horizontal diameter. Channels and branches should be benched up at least to the top of the outgoing pipe and at a slope of 1 in 12. The benching should be rounded at the channel with a radius of at least 25mm.

Foundations Concrete strip foundations (Grade C30), unless specified or agreed otherwise, sized as shown on drawings (generally 600 x 225mm to cavity walls), minimum 750mm below ground level and to approval of Local Authority Building Control Officer. Foundations to be taken below invert level of any adjacent drainage.

Ground Bearing Concrete Floor Slab Altro Pisces safety flooring to shower room laid in accordance with the manufacturers recommendations on 50mm sand/cement screed on 100mm ground bearing concrete slab on polythene vapour controll layer on 100mm Celotex GA4000 insulation board (25mm, upstand to perimeter to prevent cold bridging)on 1200 gauge DPM over-lapped with DPC on min. 150mm, well consolidated hardcore blinded with sand. Floor to achieve 'U' Value of 0.18 W/m2k.

Cavity Wall Construction Render and dash finish to match existing on dense concrete blockwork or facing brickwork to match existing, 50mm clear cavity, 75mm Celotex CW4000, dense concrete blockwork with 13mm render and skim finish. 25mm check rebates to wall reveals. Cavity wall to achieve 'U' value of 0.21W/m2k. Stainless steel wall ties bedded minimum 50mm into bed joint of each leaf with retaining clips to hold insulation boards fixed @ maximum 750mm c/c horizontally and 450mm c/c vertically and additional ties within 225mm of reveals to unbonded openings. Furfix or similar approved stainless steel wall connectors fixed to manufacturers recommendations. Break through into existing cavity where applicable to maintain continious cavity and install vertical DPC. Lay horizontal DPC in continuous lengths with minimum 100mm laps and full laps at angles. DPC width at least full width of masonary leaf. DPC level to be minimum 150mm above GL. Vertical insulated DPC's installed to jambs of openings. Standard horizontal DPC's to lintels over window and door openings.

Lintels External cavity wall openings to be spanned with insulated prefabricated stainless steel lintels to BS EN 845-2, sized to Local Authority Building Control Officer approval with minimum end bearings of 150mm and tray DPC to overlap openings 225mm minimum either side, complete with stop ends and proprietary PVC weepholes over heads of openings @ 450mm c/c. Internal wall openings to be spanned with 100 x 140mm prestressed concrete lintels with minimum 150mm end bearings. Lintels to approval of the Local Authority Building Control Officer.

Radon Barriers at DPC level (where required by BCO) Incorporate Petheleyne radon prevention barriers in accordance with manufacturers instructions. Observe good building practice and wet bed all barriers in accordance with codes of practice regarding installation of damp proof courses. Ensure all junctions between barrier lengths and mouldings are well lapped and sealed using radon barrier sealing tape.

Pitched Roof Construction - slope to match existing. Composite slates or concrete interlocking roof tiles with plain hip/ridge tiles (as specified on drawing) to match existing on 50 x 25mm treated battens on reinforced sarking felt on treated softwood rafters or prefabricrted trussed rafters by specialist. Rafters to be supported on 100 x 75mm treated softwood wall plate bedded in mortar and strapped down @ maximum 2000mm c/c. Tiles/slates fixed strictly in accordance with the manufacturers recommendations. 100mm. Rockwool insulation laid between ceiling joists with 200mm. Rockwool insulation laid over ceiling joists to acheive 'U' Value of 0.15W/m2k. Form opening for access into roof space and provide insulated ceiling access panel. Install PVCu fascia boards & PVCu ventilated soffits equal to 25mm continuous air gap or over-fascia ventilation to comply with the latest edition of the Building Regulations Approved Document Part F. Mono-pitch roofs to have abutment ventilation pack with minimum 5mm continuous ventilation. Rainwater gutters to be 100mm PVCu to match existing with 68mm dia downpipes all clipped and bracketed in accordance with the manufacturers recommendations.

Timber sizes to approval of the Local Authority Building Control Officer.

External Door Supply and fix new PVCu. door and frame , internally sealed and double glazed with low E glass. Max.'U' Value 1.6W/m2k. with multi lock system. Include for all furniture fixings,Stormguard AM3 or similar approved low level threshold low level threshold where required, mastic seal and making good to reveals and existing finishes where applicable.

Windows Supply and fix new internally sealed double glazed PVCu. window with low E glass. Max. 'U' Value 1.6W/m2k. Windows to provide $\frac{1}{10}$ th. daylight and $\frac{1}{10}$ th. ventilated opening area of the floor area or the room served with 4000mm2 background ventilation to shower room and kitchens and 8000mm2 to habitable rooms. Include all furniture, fittings, plastic window boards and mastic seal and make good to reveals and existing finishes.

Internal Doorset Internal 838mm wide flush door with internal skeleton or cellular core, hardboard faced both sides, lipped on two long edges including all door furniture and hinges with 100 x 32mm lining and 35 x 12mm doorstops.

Timber Stud Partition Wall 47 x 75mm treated sawn softwood sole plates, heads and studs @ max 450mm centres. Horizontal noggins @ max 600mm centres staggered vertically. Additional studs at plasterboard joints and fixing points etc. 12.5mm plasterboard and skim both sides with 75mm Rockwool insulation between studs.

Electrical Installation All works to be in accordance with BS 7671 (the IEE Wiring Regulations). Installation to be carried out by Competent Persons as defined in the Building Regulations Approved Document P. Power points & light switches to be positioned 1000mm above FFL.

Lighting Low energy sealed bulkhead light fitting and pull switch in shower room. Low energy pendant light and switch in bedroom / lobby.

Heating Extend existing C.H. pipework to new radiators capable of maintaining temp. of 18 deg. C. when external temp. is -1 deg. 'C'.

Paths Form new 1200mm wide concrete path as follows:- 75mm thick concrete slab 1:2:4 mix on 75mm well consolidated hardcore. Form non-slip serrated surface as indicated with smooth trowel finish to edg. to finish 150m. below int. floor level and gently fall away from extension.

Steps Form new concrete steps with min. 75mm thick concrete 1:2:4 mix on min 75mm well consolidated hardcore Treads min 300mm with slip resistant surface & risers max 150mm

Concrete Ramps Form new concrete ramp with 1:12 gradient as follows:- 75mm thick concrete slab 1:2:4 mix on 75mm well consolidated hardcore. Form non-slip serrated surface. Form new concrete platform at top (to finish level with internal ground floor slab), bottom and changes in direction of ramp. 100mm upstand kerb to exposed edges of ramp.

External Handrails (on exposed edges of ramps/steps) Supply and fix 40mm dia. galv. steel handrails. Handrail supported at 850mm. above path by galv. steel posts. Posts to be set in ground to min. depth of 210mm and surrounded in conc. (1:3:6 mix) min. cover 100mm. Depth and thickness of conc. to be increased where ground conditions necessitate to achieve lateral support.

Painting & Decorating Internally apply, 1 mist and 2 full coats emulsion to walls and ceilings. Knot, prime and stop and apply 2 coats undercoat and 1 coat gloss to wood surfaces.

Rev	Details	Dr	Date



Neath Port Talbot
Castell-nedd Port Talbot
County Borough Council Cyngor Bwrdeistref Sirol

Neath Port Talbot Castell -nedd Port Talbot
County Borough Council Cyngor Bwrdeistref Sirol
Social Services, Health and Housing
Housing Renewal and Adaptations Service
Tregelles Court
Neath Abbey Road
Neath Abbey
Neath
SA10 7DF

Project

57 Glan yr Afon
Ystalyfera
SA9 2HA

Porch Extension
Specification

Drawn	SJL	Checked		Approved	
Date	Sept19	Date		Date	
Scales	1:50				
Drawing No.		DFG4405/03			