



Customer:	John Williams ECO2 Ltd Vision House Oak Tree Court, Mulberry Drive Cardiff Gate Business Park Cardiff CF23 8RS	Testing Facility:	ESG Unit 12 Moorbrook Southmead Industrial Estate Didcot Oxfordshire OX11 7HP
Quotation Number:	DIF-ANU-8557 (Period 12)	Samples Received:	24 March 2017
Customer Order Number:		Analysis Completed:	30 March 2017
Customer Reference:		Report Date:	05 April 2017

Nitrogen Dioxide Diffusion Tube Analysis Report

The samples have been analysed in accordance with ESG's standard operating procedure ANU/SOP/1015 Issue 1. This method meets the guidelines set out in DEFRA's 'Diffusion Tubes For Ambient NO₂ Monitoring: Practical Guidance.'

The tubes were prepared by spiking acetone:triethanolamine (50:50) onto the grids prior to the tubes being assembled. The tubes were desorbed with distilled water and the extract analysed using a segmented flow autoanalyser with ultraviolet detection. All samples were received in good condition, unless otherwise stated in the comments field of results table. Please note:

- (i) As set out in the practical guidance, the results were initially calculated assuming an ambient temperature of 11°C, the reported values **have** been adjusted to 20°C to allow for direct comparison with EU limits.
- (ii) The reported results have not been bias adjusted.

This analysis of diffusion tube samples to determine the amount of nitrogen dioxide present on the tube is within the scope of our UKAS schedule. Any further calculations and assessments requiring exposure details and conditions fall outside the scope of our accreditation. In the WASP intercomparison scheme for comparing spiked Nitrogen Dioxide diffusion tubes, ESG currently holds the highest rank of a **Satisfactory** laboratory.

Approved By

Sandy Hall
Analyst



Sample Number	Site	Date and Time ON	Date and Time OFF	Exposure Time (Hours)	Total µg	µg m ⁻³	ppb	Comments
ECO/16A/NA12S1	Margam	15/01/2017 09:00	21/02/2017 09:00	888.00	2.61	42.1	21.9	
ECO/16A/NA12S2	Margam	15/01/2017 09:00	21/02/2017 09:00	888.00	2.51	40.6	21.1	
ECO/16A/NA12S3	Margam	15/01/2017 09:00	21/02/2017 09:00	888.00	2.4	38.7	20.1	