



Roger Casey Associates

Consulting Civil & Structural Engineers

Ty Mansel, 6 Mansel Street, Carmarthen,
Carmarthenshire SA31 1PX
T: 01267 222 646

Units 10 & 11, Merlin's Court, Winch Lane,
Haverfordwest, Pembrokeshire SA61 1SB
T: 01437 762 795

E: office@rca-eng.co.uk
W: www.rca-eng.co.uk

Project:

**RESIDENTIAL DEVELOPMENT OFF LLYS WERN, NEATH, NEATH
PORT TALBOT. SA10 7PR**

Job No.:

20139

Date:

10.01.2019

Page :

1 of 1

Schedule No. : **FW1**

Title:

**Foul Water Drainage
Chamber Schedule**

Rev: -

Status: -

CHAMBER	COVER	INVERT	PIPE	INVERT	SOFFIT	CHAMBER	CHAMBER	CHAMBER	COVER	COVER	COMMENTS /	REV.
REF.	LEVEL	LEVEL	DIA. (mm)	DEPTH	DEPTH	SIZE (mm)	TYPE	MATERIAL	SIZE	GRADE	ADDITIONAL INFORMATION	
F1	41.440	40.740	100	0.700	0.600	450	3	PLASTIC	450mm	A15		
F2	41.440	40.705	100	0.735	0.635	450	3	PLASTIC	450mm	A15		
F3	41.557	40.658	100	0.899	0.799	450	3	PLASTIC	450mm	A15		
F4	42.007	40.641	100	1.366	1.266	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F5	41.890	40.595	100	1.295	1.195	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F6	41.890	40.575	100	1.315	1.215	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F7	42.040	40.467	100	1.573	1.473	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F8	42.040	40.452	100	1.588	1.488	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F9	42.146	40.408	100	1.738	1.638	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F10	42.596	40.394	100	2.202	2.102	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F11	42.490	40.340	100	2.150	2.050	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F12	42.490	40.325	100	2.165	2.065	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	
F13	42.490	40.260	100	2.230	2.130	450	3	PLASTIC	450mm	A15	350mm OPENING RESTRICTION	

NOTES

1. WHERE DEPTH TO INVERT GREATER THAN 1m ON TYPE 3 AND 4 CHAMBERS - PROVIDE ACCESS RESTRICTOR REDUCING APERTURE TO 350mm DIAMETER OR 300x300mm.
2. ALL CONNECTION INVERT LEVELS WITH EXISTING DRAINAGE NETWORKS AT POINT OF DISCHARGE, DIVERSION, ETC. SHALL BE CHECKED AND VERIFIED PRIOR TO COMMENCEMENT OF ANY PIPE LAYING WORKS BY THE CONTRACTOR.
3. REFER TO RCA DRAINAGE CONSTRUCTION DETAILS FOR PLASTIC CHAMBER AND ALL OTHER NOTES - IF IN DOUBT ASK. NO EXTERNAL BACKDROP ON PLASTIC CHAMBERS.