



Access to Park

Work shall entail:

- 1. Excavation of grass soil to 300mm depth*
Installation of 250mm RC concrete base & base plate. All in accordance with Drgs SK200911-2 Sculpture Base Detail & SK200911-3 Sculpture Base Detail
- 2. Supply and installation of sculpture
All in accordance with Drg V8 Salmon Interpretation
- 3. Filling around sculpture base - Type 1 Material with 50mm AC Asphalt Concrete finished with Resin Bound Gravel (by Addagrip colour Autumn Toffee) all to match existing adjacent path surfaces

Note: Contamination on Site is **beneath** an existing geotextile membrane that is min 300mm below existing finished ground level and shall remain on situ. **No works shall take place beneath that membrane (see Drg SK200911-2)** where, item 3 above shall complete the work ensuring **no** contamination pathways exist post completion



BAR SCALE

GREEN PARK STREET

VIEWING AREA WITH SEATS

WILDFLORA

GRASS

Existing Path

RIVER AFAN

Top Wall
c.8.528

Top Wall
c.8.575
GL 7.625

