

Reduction of overhanging trees.

Operatives to sign into store before works commence. Area below the trees to be cordoned off from vehicles and general public. NTPC trained climbers will climb tree on right side of car park and remove 2 limbs that are hanging towards resident property. Branches will be lowered to ground by rope. Remaining trees lift low branches that are growing towards carpark. Once all trees are pruned chip waste onto vehicle and remove from site. Leave site in a clean state and remove cordoned area.

