



office of origin

REINFORCEMENT**Swansea****SCHEDULE**

Project Rebar Detail to Ret Wall	Project No C1447	Date 10/11/2020
Schedule no S-201/ 1		Status of 2

to PLOT 2

Drawn by MD	Checked by TH	Revision	Date	Total Wt kg 3428.666
-----------------------	-------------------------	----------	------	--------------------------------

Member	Mark	Type & Size	No. off	No. in each	Total no	Length mm	Shape Code	A mm	B mm	C mm	D mm	E/R mm	Wt kg	Rev Letter
BASE	01	H16	1	111	111	2825	21	240	2400	(240)			495.45	
	02	H10	1	111	111	2850	21	240	2400	(240)			195.19	
	03	H16	1	23	23	2225	11	240	(2000)				80.86	
	04	H16	1	8	8	1525	11	240	(1300)				19.28	
	05	H10	1	23	23	2225	11	240	(2000)				31.58	
	06	H10	1	8	8	1525	11	240	(1300)				7.53	
	07	H10	1	52	52	1200	21	500	220	(500)			38.50	
	08	H10	1	156	156	4000	00						385.01	
	09	H10	1	26	26	1950	15	790	650	(1150)			31.28	
	10	H10	1	26	26	3150	15	1400	1150	(1750)			50.53	
WALL	08	H10	1	128	128	4000	00						315.90	
	11	H16	1	130	130	1375	11	1100	(300)				282.43	
	12	H12	1	130	130	1400	11	1100	(300)				161.62	
	13	H12	1	130	130	1375	21	600	200	(600)			158.73	
	14	H16	1	120	120	3000	00						568.80	
	15	H12	1	120	120	3000	00						319.68	
	16	H10	1	64	64	3000	00						118.46	
	17	H10	1	61	61	1050	21	450	170	(450)			39.52	
	18	H10	1	64	64	900	15	300	250	(600)			35.54	
	19	H10	1	32	32	1100	15	550	450	(550)			21.72	
	20	H10	1	32	32	1600	11	800	(800)				31.59	
	21	H10	1	64	64	1000	11	800	(200)				39.49	

Status: P Preliminary T Tender C Construction

REINFORCEMENT

SCHEDULE

Date **10/11/2020**

Schedule no **S-201/ 2** of 2 Status

Drawn by	Checked by	Revision	Date	Total Wt kg
MD	TH			127.595

[illegible]

Status: P Preliminary T Tender C Construction