



JP Concrete

DESIGN | SUPPLY | INSTALL

BOLT DOWN RETAINING WALLS

www.jpconcrete.co.uk



Expert advice

Our product specialists will advise on the most cost-effective precast solution for your project.



Quality Assured

We are proud to hold ISO: 9001, 14001 & 18001 Constructionline Silver Membership &SSIP



Precast solutions

Our skilled teams of engineers, groundworkers & precast installers cover the entire project life-cycle.

BOLT DOWN RETAINING WALLS

Concrete bolt down retaining wall units are a versatile product which can be used to store and retain a wide variety of materials.

- ✓ Retaining Wall Heights 1.0m to 3.75m
- ✓ 90 & 45 Degree Corner Units
- ✓ 10kN/m² Surcharge Capacity
- ✓ C50 Concrete Mix Strength
- ✓ Installation Service Available

Features

Corner units are available in 90° & 45° for all heights, enabling you to construct bays with ease.

Mastic application, or other sealing systems, can be applied to joints to make bolt down retaining wall units suitable for storing liquids.

Wall units are manufactured under factory controlled conditions, designed to relevant British & Eurocode standards and are CE marked.



The L-shape retaining wall units are suitable for a wide range of applications including:

- Storage Bays
- Earth Retention
- Aggregate Bays
- Salt Barns
- Waste & Recycling
- Flood Defence
- Bund Walling

We provide a full design, construction & installation service for all of our products, enabling us to offer turnkey solutions. Call the team today to discuss your project. 01158 220 282

PRODUCT SPECIFICATIONS

Below is a table outlining the characteristics of the concrete bolt down retaining wall.

Here you can find information on concrete strength, material density and surcharge capacity.

Wall units are manufactured under factory control, have been designed to relevant British (BS) & Eurocode (EN) standards and are CE marked.

If you require any further details please contact us and one of our product experts will be happy to provide more information.

Concrete Strength	C50	Material Density	18	Surcharge Capacity	10	Design Life	50
Compressive strength of concrete after 28 days of curing.		Maximum material density of retained material, measured in kN/m^3		Maximum surcharge capacity of precast element, measured in kN/m^2		Number of years precast element has been designed for.	
Connection		Edge Detail		Concrete Finish	A	Fire Resistance	N/A
Precast elements have flat sides & do not interlock.		Square edges enable close alignment & reduced movement joints between units.		Smooth mould finish Type A to precast element, defined in British Standards		Number of minutes precast element would provide fire resistance.	
Reinforcement Cover	30	Tolerances	6	Foundation Type	RC	Retained Face	DL
Minimum cover to steel reinforcement in precast element, measured in mm.		Typical manufacturing tolerances & dimensional variations +/- in mm.		A reinforced concrete (RC) foundation is required for installation.		Double Load - Precast element is suitable for retaining material on both faces	

PRODUCT RANGE

In addition to the standard units shown below, 90° & 45° corner units are also available for all heights, enabling you to construct storage bays with ease.

Installation of the precast units is quick and easy. The elements are drilled and fixed to a reinforced concrete foundation or concrete floor slab, using a resin anchor system. Once the units are secured to the foundation, no additional fixing is required, making them the ideal solution when you have no existing steelwork to fix to.

1m	1.5m	1.75m	2m	2.5m	3m	3.75m
						
Height 1000mm	Height 1500mm	Height 1750mm	Height 2000mm	Height 2500mm	Height 3000mm	Height 3750mm
Length 1000mm	Length 1000mm	Length 1000mm	Length 1000mm	Length 1000mm	Length 1000mm	Length 1000mm
Width 500mm	Width 750mm	Width 875mm	Width 1000mm	Width 1250mm	Width 1500mm	Width 1875mm
Weight 394kg	Weight 631kg	Weight 761kg	Weight 890kg	Weight 1310kg	Weight 1740kg	Weight 2596kg



Get clarity

Visit our new website and get to grips with our precast products in detailed 3D



NOTTINGHAM

DEVON

SUSSEX

Get a FREE quotation or advice
Call **01158 220 282** or
email: **info@jpconcrete.co.uk**

Head Office

The Quay, Plymouth Road, Tavistock,
Devon, PL19 8AB

Manufacturing

Staunton Works, Staunton in the Vale,
Nottingham NG13 9QB

Sales & Marketing

Newhaven Enterprise Centre, Newhaven,
East Sussex BN9 9BA