0m 10m 20m 50m

N

Notes:-

1. This drawing and all information contained thereon is intended for Planning purposes only. NOT FOR CONSTRUCTION;
2. All highway geometry, gradients and levels are subject to the approval of the Local Highway Authority;
3. Finished carriageway levels within shared-surface areas and raised tables shall be 100mm higher than the alignment contours shown;
4. Levels of existing surface water culvert to be confirmed.

KEY

- 62.90 — Proposed Ground Level
- 300rw — Masonary Retaining Wall (Height Indicated)
- 300e — Exposed Facing Brickwork (Height Indicated)
- 1 in 2 max Embankment
- 64.300 — Finished Floor Level
- 3s — Steps (No. Indicated)

MEADOW ROAD

EAGLEBUSH HOUSE

DETENTION POND

DUAL USE OPEN SPACE & ATTENUATION AREA

Proposed Attenuation Pipe Network (Indicative Only)

Proposed Foul Water Pipe Network (Indicative Only)

1 in 2 max batter

G10-Ash

See 2430-630 for Site Sections

This drawing is copyright and its use or reproduction without the permission of Spring Design Consultancy Limited. All rights are reserved until invoices are paid in full. No responsibility will be taken for any design used for construction prior to receipt of relevant approvals.

rev	date	description	by
B	09.04.21	Updated to suit revised site boundary.	MCC

rev	date	description	by
-	-	-	-

Status: **PLANNING**

Drawn: RMJ
Checked: MCC
Date: December 2020
Scale: 1:250

Client: Jones Brothers & Tai Tarian
Project: Meadow Road, Neath
Title: External Engineering Works
Ref: 2430-526
Rev: B

spring design
Unit 3 Chapel Barns | Merthyr Mawr
Bridgend | CF32 0LS | 01656 656267
mail@spring-consultancy.co.uk