

APPENDIX A – Flooding Emergency Plan

It is anticipated that with modern weather and tidal forecasting and the position of the site in relation to the potential source of flooding that a period of at least 4 hrs would be available for completing the tasks outlined below. The site operator would maintain membership with NRW's flood warning system and any local systems which have a particular regard to the potential for tidal flooding.

In the event that there is a high risk of flooding actions would be taken.

1. Evacuate non-essential personnel to safe area.
2. Ensure all site records are placed in higher area or removed from site.
3. Seal surface and foul water drainage systems.
4. Remove all vehicles from site to safe areas.
5. Disconnect all electrical equipment and ensure that where possible vulnerable items are removed or placed above projected flooding levels.
6. Evacuate all remaining personnel and customers to safe areas.
7. Isolate all incoming services and secure site.

After flooding has receded the following would take place:

1. Check integrity of all structures on site.
2. Check equipment.
3. Check drainage and reconnect services.
4. Clean up if necessary.