

QuadConsult Limited
Columbus House
Village Way
Greenmeadow Springs Business Park
Cardiff
CF15 7NE

Tel: +44 (0)29 2077 9644
email: contactus@quadconsult.co.uk
Web: www.quadconsult.co.uk

Former School Site, Gwaun-Cau-Gerwen

Drainage Strategy and SuDS Compliance Statement

on

Proposed Residential Development

for

Mr Dylan Davies

Date December 2021

Document ref no. 21505-R-601-Drainage Strategy &
SuDS Compliance Statement - 0



Directors
Chris Usher BSc(Hons) CEng FStructE MICE AaPS
Andrew Villis
Consultant
Steve McCarthy BEng(Hons) MSc CEng MICE MCIHT

QuadConsult Limited registered in England and Wales reg.no. 06880193
Columbus House, Village Way
Greenmeadow Springs Business Park
Cardiff, CF15 7NE

Former School Site, Gwaun-Cau-Gerwen
Drainage Strategy and SuDS Compliance Statement

Document Control

Responsible for	Job Title	Name	Date	Signature
Content	Civil Engineer	Mark Llewellyn	20 Dec 2021	
Checked	Civil Engineer	Matthew Bartlett	20 Dec 2021	
Approval	Director	Andrew Willis		
Copyright:	QuadConsult ©2021	Document Reference:	21505-R-601-Drainage Compliance Statement -0	Strategy & SuDS
Signatories in this approval box have checked this document in line with the requirements of QuadConsult QMS Procedures				

Revision History

Revision	Date	Purpose/Status	Approved
0	20 December 2021	Comment	
A			
B			
C			
D			
E			
F			

Distribution

	Function Title	Company	Name
1	SAB Officer	NPT County Council	
2			
3			

CONTENTS

Section	Item	Page
1.0	INTRODUCTION	3
2.0	DRAINAGE	4
3.0	COMPLIANCE WITH THE NATIONAL SuDS STANDARDS S1 – S6	6
Appendix A	Existing Site Location & Layout Plan	
Appendix B	Existing Site Topographical Survey	
Appendix C	Existing Culvert Survey (To Follow)	
Appendix D	Proposed Site Layout	
Appendix E	Proposed Drainage Strategy Plan	
Appendix F	Proposed Landscape Architects Layout	
Appendix G	Existing Brownfield Discharge Rates	
Appendix H	Proposed Surface Water Calculations	
Appendix I	Infiltration Testing Results	

This document is for the exclusive use of the client and should not be used in whole or in part by any third parties without the express written permission of QuadConsult Limited.

1.0 INTRODUCTION

The site is located off Water Street in Gwaun-Cau-Gerwen (Refer to Figure 1), part of the site previous housed a former school building with associated hard surfaced yard. The existing school site (0.22ha) is fully impermeable hardstanding construction. The additional area of the site is a heavily vegetated / woodland area (0.125ha). The proposal is to clear both areas of the site and construct 10 new dwellings in an arrangement of 5 pairs on semi-detached houses. 6 dwellings will be sited directly off Water Street with the other 4 being accessed via a proposed shared drive off Water Street (Refer to Appendix A for site layout plan).



2.0 DRAINAGE

A schematic drainage layout is appended, detailing the proposals for the drainage strategy outlined in the following sections.

2.1 Existing Surface Water Drainage

The existing school site (0.22ha) is fully impermeable construction draining via a series of gullies and piped network into the culvert located within Water Street. The Culvert discharges into the Garnant Watercourse located circa 70m to the West of the site. The remaining 0.125ha is a currently heavily vegetated greenfield area. The existing brownfield discharge rates for the school site (0.22ha) are calculated as follows (Refer to Appendix G for full calculations).

1 Year	-	22.2l/s
30 Year	-	50.8l/s
100 Year	-	64.0l/s

2.2 Proposed Foul Drainage

The 6 proposed dwellings fronting Water Street will connect directly on the Welsh Water Foul Sewer located within the road. The remaining 4 proposed dwelling will connect on the existing Welsh Water combined sewer crossing the site in the Northwest corner. The combined proposed Foul discharge rates for the development are as follows: -

0.076l/s average flow
0.46l/s peak flow

Based on SFA 7th edition: -

222 l/per/day
3 persons per house
Peak Flow Factor of 6

2.3 Proposed Surface Water Drainage

Permeability tests undertaken on site demonstrated that the ground was not suitable for drainage systems based on fully permeable ground techniques. Further geotechnical site investigation including infiltration testing to BRE365 will be undertaken as part of the site redevelopment

The surface water drainage for the proposal will comply with SAB/SuDS protocols, and work within the site layout & constraints of the proposed development.

The proposed combined surface water discharge rate from the development is 15.5l/s, allowing for a 100-year storm event with 40% allowance for climate change. Utilising the attenuation volumes offered through the sub-base makeup of both private and shared drive areas of the development. The proposed 15.5l/s offers a 30% betterment over the existing 1-year surface water discharge rates. The proposal also offers a betterment of over 75% over the existing 100-year storm event discharge rates. Plots 1-6 will incorporate individual discharge rates of max 1.0l/s for the 100 year event with 40% climate change allowance. Attenuation will be sited within the private drive subbase and individual plot flow control devices prior to direct connections into the existing culvert. This arrangement will allow the SuDs features and infrastructure to be kept private under the responsibility of the homeowners. Plots 7-10 will discharge into their private drives before connecting into the shared drive subbase, again allowing the plot infrastructure to be kept private. The proposed discharge rate for plots 7-10 and the shared drive will be max 9.5l/s, offering a total combined discharge rate of 15.5l/s for the 100 year event plus 40% climate

change allowance. The shared drive will be offered for adoption to the local authority SAB in accordance with Welsh Government statutory guidance.

The following sections detail the design principles that will be incorporated in the development proposals for the scheme, and the measures incorporated to satisfy the requirements for future SAB approval.

3.0 COMPLIANCE WITH THE NATIONAL SuDS STANDARDS S1 – S6

3.1 Standard S1 – Surface Water Run-off Destination

Priority Level 1

The use of a SuDS planter is proposed to intercept roof runoff and act as a point of source control. This will allow a limited re-use of rainwater to facilitate the planter and associated flora.

Priority Level 2: Infiltration to Ground

Ground conditions have been demonstrated to be unsuitable for the use of drainage systems based on permeable ground techniques. Further testing will be carried out to confirm ground water level.

Drainage blankets have been proposed beneath parking areas, which will principally serve to improve water quality for the runoff from these surfaces and act as primary attenuation facilities.

Priority Level 3: Discharge to a Surface Water Body

As outlined above, the provision will be to collect, treat, attenuate, and discharge to the culvert running in Water Street. This discharge route offers a direct connection and discharge to the Garnant Watercourse located circa 70m to the west of the site

Priority Level 4: Discharge to a Surface Water Sewer, Highway Drain, or other Drainage System

Deemed not required/applicable for this development.

Priority Level 5: Discharge to a Combined Sewer

Deemed not required/applicable for this development.

3.2 Standard S2 – Surface Water Runoff Hydraulic Control

SuDS System Sizing for 100 Year Return Period Rainfall Event, Plus Climate Change

It is proposed that the attenuation system be designed such that it is sufficient to store critical storm duration flows in the 100yr+40% event. Calculations are appended. As noted above there have been no reductions made to the sizing of the attenuation to reflect reductions afforded by the rain gardens or operation of the SuDS planters. Therefore, allowing for a worst-case scenario.

First 5mm Interception

Interception mechanisms will be required to ensure compliance with the requirement of zero runoff for the first 5mm rainfall for 80% of storm events during the summer and 50% in winter.

The provision of SuDS planter features and rain gardens along with flows through permeable drive subbase will contribute to the objective of first 5mm interception. Deemed to comply with the SAB standards.

Exceedance/Blockage

Any exceedance flows will follow surface topography. The topography is such that any excess flows will be directed in a north western direction towards the existing watercourse.

3.3 Standard S3 – Water Quality

The proposed SuDS treatment train devices (SuDS planters, Rain Gardens and Drainage Blankets) will deliver the requisite cleansing and filtration of runoff for this residential (low pollution hazard level) development.

3.4 Standard S4 – Amenity

The soft suds features (SuDS planters, Rain Gardens) will be carefully designed and integrated into the landscaping scheme for the development, to promote aesthetics and well-being as well as any designed drainage function.

Proposed soft landscaping & planting will be augmented and included within the development proposals (refer to Appendix F).

3.5 Standard S5 - Biodiversity

The soft suds features (Bio-Retention Planters, Rain Gardens etc) will be carefully designed with gradients/profiles, planting species and soil properties selected to ensure suitable habitat is delivered to promote biodiversity. Planting information is included within the SUDS planter operational information. These proposals will augment the green infrastructure element of the design proposals to demonstrate a robust response to this Standard.

3.6 Standard S6 - Construction, Operation and Maintenance and Structural Integrity


Much of the infrastructure maintenance will be dealt with at a property level as many of the systems employed are contained within a single curtilage application. The online attenuation within the shared drive sub-base) will be offered for adoption through the SAB application process if agreed during pre-SAB discussions. All of the proposed SuDS infrastructure is in accessible areas for ease of maintenance. The surface water network including any land drainage will be designed to be fully roddable and jettable, with suitably positioned rodding eyes and mini-access chambers.

The suds devices are low maintenance surface/shallow items with established regular maintenance regimes.

The proposed design solution has been designed in accordance with the SuDS manual and is generally served by shallow SuDs features and accessible details. There are no inherent safety issues with the proposed scheme.

The on-property drainage infrastructure will be managed by the Tenant. The principal issue is the management of the SuDS planters, which primarily involves periodic inspection to check the overflows are clear and ensure the free-flowing operation. These inspections will also serve to monitor the build-up of any silt in the system to facilitate any cleaning required.

**APPENDIX A
EXSITING SITE LOCATION AND LAYOUT PLAN**




**APPENDIX B
EXISTING SITE TOPOGRAPHICAL SURVEY**



**APPENDIX C
EXISTING CULVERT SURVEY**


**APPENDIX D
PROPOSED SITE LAYOUT**



**APPENDIX E
PROPOSED DRAINAGE STRATEGY PLAN**



**APPENDIX F
LANDSCAPE ARCHITECTS LAYOUT PLAN**



**APPENDIX G
EXISTING BROWNFIELDED SURFACE WATER DISCHARGE RATES**

QuadConsult Ltd		Page 1
Columbus House	Former School Site	
Greenmeadow Springs Business...	GCG	
Cardiff, CF15 7NE	Ammanford	
Date 15/12/2021 10:57	Designed by ML	
File 21505-CA-702-BROWNFIELD...	Checked by	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	PIMP (#)	100
MS-60 (mm)	20.000	Add Flow / Climate Change (#)	0
Ratio R	0.202	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	65	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.156	4-8	0.044

Total Area Contributing (ha) = 0.200

Total Pipe Volume (m³) = 0.398

©1982-2020 Innovyze

QuadConsult Ltd		Page 2	
Columbus House Greenmeadow Springs Business... Cardiff, CF15 7NE		Former School Site GCG Ammanford	
Date 15/12/2021 10:57 File 21505-CA-702-BROWNFIELD...		Designed by ML Checked by	
Innovyze		Network 2020.1.3	
1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm			
Simulation Criteria			
Areal Reduction Factor 1.000		Additional Flow - % of Total Flow 0.000	
Hot Start (mins) 0		MADD Factor * 10m³/ha Storage 2.000	
Hot Start Level (mm) 0		Inlet Coefficient 0.800	
Manhole Headloss Coeff (Global) 0.500		Flow per Person per Day (l/per/day) 0.000	
Foul Sewage per hectare (l/s) 0.000			
Number of Input Hydrographs 0		Number of Storage Structures 0	
Number of Online Controls 0		Number of Time/Area Diagrams 0	
Number of Offline Controls 0		Number of Real Time Controls 0	
Synthetic Rainfall Details			
Rainfall Model FSR		Ratio R 0.200	
Region England and Wales Cv (Summer)		0.750	
MS-60 (mm) 20.100 Cv (Winter)		0.840	
Margin for Flood Risk Warning (mm) 300.0		DVD Status OFF	
Analysis Timestep		Fine Inertia Status OFF	
DTS Status		ON	
Profile(s)		Summer and Winter	
Duration(s) (mins)		15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080	
Return Period(s) (years)		1, 30, 100	
Climate Change (%)		0, 0, 0	
US/MH		Return Climate	
PN Name Storm		First (X) First (Y) First (Z) Overflow	
		Surcharge Flood Overflow Act.	
		Water Level	
		(m)	
S1.000 S1 15 Winter		1 +0% 30/15 Summer 156.113	
S1.001 S2 15 Winter		1 +0% 30/15 Summer 156.013	
Surcharged Flooded		Half Drain Pipe	
US/MH Depth Volume Flow / Overflow Time Flow Level		Status Exceeded	
PN Name (m) (m³) Cap. (l/s) (mins) (l/s)			
S1.000 S1 -0.112 0.000 0.49		21.9 OK	
S1.001 S2 -0.112 0.000 0.50		22.2 OK	
©1982-2020 Innovyze			

QuadConsult Ltd			Page 3						
Columbus House Greenmeadow Springs Business... Cardiff, CF15 7NE			Former School Site GCG Ammanford						
Date 15/12/2021 10:57 File 21505-CA-702-BROWNFIELD...			Designed by ML Checked by						
Innovyze			Network 2020.1.3						
30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm									
Simulation Criteria									
Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000									
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000									
Hot Start Level (mm) 0 Inlet Coefficient 0.800									
Manhole Headloss Coeff. (Global) 0.500 Flow per Person per Day (l/per/day) 0.000									
Foul Sewage per hectare (l/s) 0.000									
Number of Input Hydrographs 0 Number of Storage Structures 0									
Number of Online Controls 0 Number of Time/Area Diagrams 0									
Number of Offline Controls 0 Number of Real Time Controls 0									
Synthetic Rainfall Details									
Rainfall Model FSR Ratio R 0.200									
Region England and Wales Cv (Summer) 0.750									
MS-60 (mm) 20.100 Cv (Winter) 0.840									
Margin for Flood Risk Warning (mm) 300.0 DVD Status OFF									
Analysis Timestep Fine Inertia Status OFF									
DTS Status ON									
Profile(s) Summer and Winter									
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080									
Return Period(s) (years) 1, 30, 100									
Climate Change (%) 0, 0, 0									
Water									
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)
S1.000	S1	15 Winter	30	+0%	30/15 Summer				156.281
S1.001	S2	15 Winter	30	+0%	30/15 Summer				156.147
Surcharged Flooded						Half Drain		Pipe	
PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Overflow Cap.	Time (mins)	Flow (l/s)	Status	Level Exceeded	
S1.000	S1	0.056	0.000	1.15		61.2	SURCHARGED		
S1.001	S2	0.022	0.000	1.14		60.8	SURCHARGED		
©1982-2020 Innovyze									

QuadConsult Ltd		Page 4					
Columbus House Greenmeadow Springs Business... Cardiff, CF15 7NE		Former School Site GCG Ammanford					
Date 15/12/2021 10:57 File 21505-CA-702-BROWNFIELD...		Designed by ML Checked by					
Innovyze		Network 2020.1.3					
<u>100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>							
<u>Simulation Criteria</u>							
Areal Reduction Factor 1.000		Additional Flow - % of Total Flow 0.000					
Hot Start (mins) 0		MADD Factor * 10m³/ha Storage 2.000					
Hot Start Level (mm) 0		Inlet Coefficient 0.800					
Manhole Headloss Coeff (Global) 0.500		Flow per Person per Day (l/per/day) 0.000					
Foul Sewage per hectare (l/s) 0.000							
Number of Input Hydrographs 0		Number of Storage Structures 0					
Number of Online Controls 0		Number of Time/Area Diagrams 0					
Number of Offline Controls 0		Number of Real Time Controls 0					
<u>Synthetic Rainfall Details</u>							
Rainfall Model FSR		Ratio R 0.200					
Region England and Wales Cv (Summer)		0.750					
M5-60 (mm) 20.100		Cv (Winter) 0.840					
Margin for Flood Risk Warning (mm) 300.0		DVD Status OFF					
Analysis Timestep Fine		Inertia Status OFF					
DTS Status ON							
Profile(s)		Summer and Winter					
Duration(s) (mins)		15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080					
Return Period(s) (years)		1, 30, 100					
Climate Change (%)		0, 0, 0					
US/MH		Return Climate	First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Level
						Overflow	Act.
S1.000	S1	15 Winter	100	+0%	30/15 Summer		156.442
S1.001	S2	15 Winter	100	+0%	30/15 Summer		156.227
US/MH		Surcharged Flooded	Half Drain		Pipe		
PN	Name	Depth	Volume	Flow / Overflow	Time	Flow	Level
		(m)	(m³)	Cap. (l/s)	(mins)	(l/s)	Status Exceeded
S1.000	S1	0.217	0.000	1.45		64.4	SURCHARGED
S1.001	S2	0.102	0.000	1.44		64.0	SURCHARGED
©1982-2020 Innovyze							

**APPENDIX H
PROPOSED SURFACE WATER CALCULATIONS**

Individual Plot (1-6) Calculations (Max discharge rate 1.0l/s)

		Quadconsult Ltd	File: 21505-CA-703-SINGLE PLOT ATTENUATIO Network: Storm Network Mark Llewellyn 20/12/2021	Page 1																																
Design Settings <table border="0"> <tr> <td>Rainfall Methodology</td> <td>FEH-13</td> <td>Maximum Time of Concentration (mins)</td> <td>30.00</td> <td>Preferred Cover Depth (m)</td> <td>0.900</td> </tr> <tr> <td>Return Period (years)</td> <td>2</td> <td>Maximum Rainfall (mm/hr)</td> <td>50.0</td> <td>Include Intermediate Ground</td> <td>✓</td> </tr> <tr> <td>Additional Flow (%)</td> <td>0</td> <td>Minimum Velocity (m/s)</td> <td>1.00</td> <td>Enforce best practice design rules</td> <td>✓</td> </tr> <tr> <td>CV</td> <td>0.750</td> <td>Connection Type</td> <td>Level Soffits</td> <td></td> <td></td> </tr> <tr> <td>Time of Entry (mins)</td> <td>10.00</td> <td>Minimum Backdrop Height (m)</td> <td>0.200</td> <td></td> <td></td> </tr> </table>					Rainfall Methodology	FEH-13	Maximum Time of Concentration (mins)	30.00	Preferred Cover Depth (m)	0.900	Return Period (years)	2	Maximum Rainfall (mm/hr)	50.0	Include Intermediate Ground	✓	Additional Flow (%)	0	Minimum Velocity (m/s)	1.00	Enforce best practice design rules	✓	CV	0.750	Connection Type	Level Soffits			Time of Entry (mins)	10.00	Minimum Backdrop Height (m)	0.200				
Rainfall Methodology	FEH-13	Maximum Time of Concentration (mins)	30.00	Preferred Cover Depth (m)	0.900																															
Return Period (years)	2	Maximum Rainfall (mm/hr)	50.0	Include Intermediate Ground	✓																															
Additional Flow (%)	0	Minimum Velocity (m/s)	1.00	Enforce best practice design rules	✓																															
CV	0.750	Connection Type	Level Soffits																																	
Time of Entry (mins)	10.00	Minimum Backdrop Height (m)	0.200																																	
Nodes <table border="1"> <thead> <tr> <th>Name</th> <th>Area (ha)</th> <th>T of E (mins)</th> <th>Cover Level (m)</th> <th>Diameter (mm)</th> <th>Easting (m)</th> <th>Northing (m)</th> <th>Depth (m)</th> </tr> </thead> <tbody> <tr> <td>S1</td> <td>0.010</td> <td>10.00</td> <td>157.300</td> <td>450</td> <td>229.202</td> <td>156.181</td> <td>0.600</td> </tr> <tr> <td>S2</td> <td></td> <td></td> <td>157.300</td> <td>450</td> <td>233.287</td> <td>156.868</td> <td>0.670</td> </tr> <tr> <td>S3</td> <td></td> <td></td> <td>157.300</td> <td>150</td> <td>234.743</td> <td>149.633</td> <td>0.794</td> </tr> </tbody> </table>					Name	Area (ha)	T of E (mins)	Cover Level (m)	Diameter (mm)	Easting (m)	Northing (m)	Depth (m)	S1	0.010	10.00	157.300	450	229.202	156.181	0.600	S2			157.300	450	233.287	156.868	0.670	S3			157.300	150	234.743	149.633	0.794
Name	Area (ha)	T of E (mins)	Cover Level (m)	Diameter (mm)	Easting (m)	Northing (m)	Depth (m)																													
S1	0.010	10.00	157.300	450	229.202	156.181	0.600																													
S2			157.300	450	233.287	156.868	0.670																													
S3			157.300	150	234.743	149.633	0.794																													
Node S2 Online Orifice Control <table border="0"> <tr> <td>Flap Valve</td> <td>x</td> <td>Invert Level (m)</td> <td>156.630</td> <td>Design Flow (l/s)</td> <td>1.0</td> <td>Discharge Coefficient</td> <td>0.600</td> </tr> <tr> <td>Replaces Downstream Link</td> <td>✓</td> <td>Design Depth (m)</td> <td>0.600</td> <td>Diameter (m)</td> <td>0.025</td> <td></td> <td></td> </tr> </table>					Flap Valve	x	Invert Level (m)	156.630	Design Flow (l/s)	1.0	Discharge Coefficient	0.600	Replaces Downstream Link	✓	Design Depth (m)	0.600	Diameter (m)	0.025																		
Flap Valve	x	Invert Level (m)	156.630	Design Flow (l/s)	1.0	Discharge Coefficient	0.600																													
Replaces Downstream Link	✓	Design Depth (m)	0.600	Diameter (m)	0.025																															
Node S1 Carpark Storage Structure <table border="0"> <tr> <td>Base Inf Coefficient (m/hr)</td> <td>0.00000</td> <td>Porosity</td> <td>0.30</td> <td>Width (m)</td> <td>5.000</td> <td>Depth (m)</td> <td></td> </tr> <tr> <td>Side Inf Coefficient (m/hr)</td> <td>0.00000</td> <td>Invert Level (m)</td> <td>156.700</td> <td>Length (m)</td> <td>4.000</td> <td>Inf Depth (m)</td> <td></td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Time to half empty (mins)</td> <td>49</td> <td>Slope (1:X)</td> <td>60.0</td> <td></td> <td></td> </tr> </table>					Base Inf Coefficient (m/hr)	0.00000	Porosity	0.30	Width (m)	5.000	Depth (m)		Side Inf Coefficient (m/hr)	0.00000	Invert Level (m)	156.700	Length (m)	4.000	Inf Depth (m)		Safety Factor	2.0	Time to half empty (mins)	49	Slope (1:X)	60.0										
Base Inf Coefficient (m/hr)	0.00000	Porosity	0.30	Width (m)	5.000	Depth (m)																														
Side Inf Coefficient (m/hr)	0.00000	Invert Level (m)	156.700	Length (m)	4.000	Inf Depth (m)																														
Safety Factor	2.0	Time to half empty (mins)	49	Slope (1:X)	60.0																															



Quadconsult Ltd

File: 21505-CA-703-SINGLE PLOT ATTENUATION

Network: Storm Network

Mark Llewellyn

20/12/2021

Page 2

Results for 2 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	S1	44	156.764	0.064	0.8	0.2171	0.0000	OK
60 minute winter	S2	44	156.764	0.134	0.9	0.0212	0.0000	SURCHARGED
15 minute summer	S3	1	156.506	0.000	0.4	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	S1	1.000	S2	0.9	0.446	0.113	0.0271	1.2
60 minute winter	S2	Orifice	S3	0.5				

Flow+ v10.3 Copyright © 1988-2021 Causeway Technologies Ltd



Quadconsult Ltd

File: 21505-CA-703-SINGLE PLOT ATTENUATIO

Network: Storm Network

Mark Llewellyn

20/12/2021

Page 3

Results for 30 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	S1	48	156.898	0.198	1.8	1.0856	0.0000	SURCHARGED
60 minute winter	S2	48	156.897	0.267	0.7	0.0424	0.0000	SURCHARGED
15 minute summer	S3	1	156.506	0.000	0.6	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	S1	1.000	S2	0.7	0.446	0.095	0.0324	2.8
60 minute winter	S2	Orifice	S3	0.7				

Flow+ v10.3 Copyright © 1988-2021 Causeway Technologies Ltd



Quadconsult Ltd

File: 21505-CA-703-SINGLE PLOT ATTENUATIO

Network: Storm Network

Mark Llewellyn

20/12/2021

Page 4

Results for 100 year +40% CC Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	S1	51	157.106	0.406	3.2	2.4380	0.0000	FLOOD RISK
60 minute winter	S2	51	157.105	0.475	1.1	0.0755	0.0000	FLOOD RISK
15 minute summer	S3	1	156.506	0.000	0.7	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	S1	1.000	S2	1.1	0.461	0.137	0.0324	5.0
60 minute winter	S2	Orifice	S3	0.9				

Flow+ v10.3 Copyright © 1988-2021 Causeway Technologies Ltd

Combined Plots (7-10) & Shared Drive Calculations (Max discharge rate 9.5l/s)

		Quadconsult Ltd	File: 21505-CA-705-Shared Drive ATTENUATION Network: Storm Network Mark Llewellyn 20/12/2021	Page 1																																				
Design Settings <table border="0"> <tr> <td>Rainfall Methodology</td> <td>FEH-13</td> <td>Maximum Time of Concentration (mins)</td> <td>30.00</td> <td>Preferred Cover Depth (m)</td> <td>0.900</td> </tr> <tr> <td>Return Period (years)</td> <td>2</td> <td>Maximum Rainfall (mm/hr)</td> <td>50.0</td> <td>Include Intermediate Ground</td> <td>✓</td> </tr> <tr> <td>Additional Flow (%)</td> <td>0</td> <td>Minimum Velocity (m/s)</td> <td>1.00</td> <td>Enforce best practice design rules</td> <td>✓</td> </tr> <tr> <td>CV</td> <td>0.750</td> <td>Connection Type</td> <td>Level Soffits</td> <td></td> <td></td> </tr> <tr> <td>Time of Entry (mins)</td> <td>10.00</td> <td>Minimum Backdrop Height (m)</td> <td>0.200</td> <td></td> <td></td> </tr> </table>					Rainfall Methodology	FEH-13	Maximum Time of Concentration (mins)	30.00	Preferred Cover Depth (m)	0.900	Return Period (years)	2	Maximum Rainfall (mm/hr)	50.0	Include Intermediate Ground	✓	Additional Flow (%)	0	Minimum Velocity (m/s)	1.00	Enforce best practice design rules	✓	CV	0.750	Connection Type	Level Soffits			Time of Entry (mins)	10.00	Minimum Backdrop Height (m)	0.200								
Rainfall Methodology	FEH-13	Maximum Time of Concentration (mins)	30.00	Preferred Cover Depth (m)	0.900																																			
Return Period (years)	2	Maximum Rainfall (mm/hr)	50.0	Include Intermediate Ground	✓																																			
Additional Flow (%)	0	Minimum Velocity (m/s)	1.00	Enforce best practice design rules	✓																																			
CV	0.750	Connection Type	Level Soffits																																					
Time of Entry (mins)	10.00	Minimum Backdrop Height (m)	0.200																																					
Nodes <table border="1"> <thead> <tr> <th>Name</th> <th>Area (ha)</th> <th>T of E (mins)</th> <th>Add Inflow (l/s)</th> <th>Cover Level (m)</th> <th>Diameter (mm)</th> <th>Eastings (m)</th> <th>Northing (m)</th> <th>Depth (m)</th> </tr> </thead> <tbody> <tr> <td>S1</td> <td>0.038</td> <td>10.00</td> <td>4.0</td> <td>157.300</td> <td>450</td> <td>229.202</td> <td>156.181</td> <td>0.600</td> </tr> <tr> <td>S2</td> <td></td> <td></td> <td></td> <td>157.300</td> <td>1200</td> <td>233.287</td> <td>156.868</td> <td>0.670</td> </tr> <tr> <td>S3</td> <td></td> <td></td> <td></td> <td>157.300</td> <td>150</td> <td>234.743</td> <td>149.633</td> <td>0.794</td> </tr> </tbody> </table>					Name	Area (ha)	T of E (mins)	Add Inflow (l/s)	Cover Level (m)	Diameter (mm)	Eastings (m)	Northing (m)	Depth (m)	S1	0.038	10.00	4.0	157.300	450	229.202	156.181	0.600	S2				157.300	1200	233.287	156.868	0.670	S3				157.300	150	234.743	149.633	0.794
Name	Area (ha)	T of E (mins)	Add Inflow (l/s)	Cover Level (m)	Diameter (mm)	Eastings (m)	Northing (m)	Depth (m)																																
S1	0.038	10.00	4.0	157.300	450	229.202	156.181	0.600																																
S2				157.300	1200	233.287	156.868	0.670																																
S3				157.300	150	234.743	149.633	0.794																																
Node S2 Online Hydro-Brake® Control <table border="0"> <tr> <td>Flap Valve</td> <td>x</td> <td>Objective</td> <td>(HE) Minimise upstream storage</td> </tr> <tr> <td>Replaces Downstream Link</td> <td>✓</td> <td>Sump Available</td> <td>✓</td> </tr> <tr> <td>Invert Level (m)</td> <td>156.630</td> <td>Product Number</td> <td>CTL-SHE-0147-9500-0600-9500</td> </tr> <tr> <td>Design Depth (m)</td> <td>0.600</td> <td>Min Outlet Diameter (m)</td> <td>0.225</td> </tr> <tr> <td>Design Flow (l/s)</td> <td>9.5</td> <td>Min Node Diameter (mm)</td> <td>1200</td> </tr> </table>					Flap Valve	x	Objective	(HE) Minimise upstream storage	Replaces Downstream Link	✓	Sump Available	✓	Invert Level (m)	156.630	Product Number	CTL-SHE-0147-9500-0600-9500	Design Depth (m)	0.600	Min Outlet Diameter (m)	0.225	Design Flow (l/s)	9.5	Min Node Diameter (mm)	1200																
Flap Valve	x	Objective	(HE) Minimise upstream storage																																					
Replaces Downstream Link	✓	Sump Available	✓																																					
Invert Level (m)	156.630	Product Number	CTL-SHE-0147-9500-0600-9500																																					
Design Depth (m)	0.600	Min Outlet Diameter (m)	0.225																																					
Design Flow (l/s)	9.5	Min Node Diameter (mm)	1200																																					
Node S1 Carpark Storage Structure <table border="0"> <tr> <td>Base Inf Coefficient (m/hr)</td> <td>0.00000</td> <td>Porosity</td> <td>0.30</td> <td>Width (m)</td> <td>3.600</td> <td>Depth (m)</td> </tr> <tr> <td>Side Inf Coefficient (m/hr)</td> <td>0.00000</td> <td>Invert Level (m)</td> <td>156.700</td> <td>Length (m)</td> <td>50.000</td> <td>Inf Depth (m)</td> </tr> <tr> <td>Safety Factor</td> <td>2.0</td> <td>Time to half empty (mins)</td> <td>24</td> <td>Slope (1:X)</td> <td>60.0</td> <td></td> </tr> </table>					Base Inf Coefficient (m/hr)	0.00000	Porosity	0.30	Width (m)	3.600	Depth (m)	Side Inf Coefficient (m/hr)	0.00000	Invert Level (m)	156.700	Length (m)	50.000	Inf Depth (m)	Safety Factor	2.0	Time to half empty (mins)	24	Slope (1:X)	60.0																
Base Inf Coefficient (m/hr)	0.00000	Porosity	0.30	Width (m)	3.600	Depth (m)																																		
Side Inf Coefficient (m/hr)	0.00000	Invert Level (m)	156.700	Length (m)	50.000	Inf Depth (m)																																		
Safety Factor	2.0	Time to half empty (mins)	24	Slope (1:X)	60.0																																			
Flow+ v10.3 Copyright © 1988-2021 Causeway Technologies Ltd																																								



Quadconsult Ltd

File: 21505-CA-705-Shared Drive ATTENUATIO

Network: Storm Network

Mark Llewellyn

20/12/2021

Page 4

Results for 100 year +40% CC Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	S1	48	157.102	0.402	16.1	5.8293	0.0000	FLOOD RISK
60 minute winter	S2	48	157.099	0.469	15.2	0.5308	0.0000	FLOOD RISK
15 minute summer	S3	1	156.506	0.000	9.5	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	S1	1.000	S2	15.2	0.572	0.225	0.1647	90.6
60 minute winter	S2	Hydro-Brake®	S3	9.5				

Flow+ v10.3 Copyright © 1988-2021 Causeway Technologies Ltd

**APPENDIX I
INFILTRATION TESTING RESULTS**

bg	Project : FORMER PRIMARY SCHOOL, GCH					Ref : 3129
	Title : TRIAL PIT LOCATIONS					
By :	Ckd :	Appd :	Date :	Doc ref :	Revision :	
Ref	Calculations					Output
The diagram is a site plan of the former County Primary School, outlined in red. Two trial pit locations are marked with blue crosshair symbols and labeled TP1 and TP2. TP1 is located in the upper right portion of the school site, and TP2 is located in the lower left portion. The school is situated on a grid of streets. Water Street runs along the bottom of the school site. To the left of the school, there are several plots numbered 22, 18, 11, and 15. To the right, there are plots numbered 5, 6, 7, and 10. The entire plan is overlaid on a grid.						

	Project : Former Primary School, CGC					Ref : 3129																										
	Title : Soakaway Test Results - TP1																															
By : HG	Ckd : NG	Appd : NG	Date : 26/03/2019	Doc ref :	Revision :																											
Ref	Calculations					Output																										
Test Photos Test Pit 1 																																
depth of pit 2500mm width of pit 450mm length of pit 1500mm																																
Test Results Test 1 <table border="1"> <thead> <tr> <th>Time</th> <th>Depth to water (mm)</th> </tr> </thead> <tbody> <tr><td>10.09</td><td>710</td></tr> <tr><td>10.26</td><td>710</td></tr> <tr><td>10.54</td><td>710</td></tr> <tr><td>11.09</td><td>710</td></tr> <tr><td>11.24</td><td>710</td></tr> <tr><td>11.39</td><td>710</td></tr> <tr><td>12.07</td><td>710</td></tr> <tr><td>13.35</td><td>710</td></tr> <tr><td>14.00</td><td>710</td></tr> <tr><td>15.05</td><td>710</td></tr> <tr><td>16.00</td><td>710</td></tr> <tr><td>16.34</td><td>710</td></tr> </tbody> </table>							Time	Depth to water (mm)	10.09	710	10.26	710	10.54	710	11.09	710	11.24	710	11.39	710	12.07	710	13.35	710	14.00	710	15.05	710	16.00	710	16.34	710
Time	Depth to water (mm)																															
10.09	710																															
10.26	710																															
10.54	710																															
11.09	710																															
11.24	710																															
11.39	710																															
12.07	710																															
13.35	710																															
14.00	710																															
15.05	710																															
16.00	710																															
16.34	710																															

	Project : Former Primary School, CGC				Ref : 3129																													
	Title : Soakaway Test Results - TP1																																	
By : HG	Ctd : NG	Appd : NG	Date : 26/03/2019	Doc ref :	Revision :																													
Ref	Calculations				Output																													
Test Photos			depth of pit 2500mm width of pit 450mm length of pit 1500mm																															
Test Pit 2																																		
			Test Results Test 1 <table border="1"> <thead> <tr> <th>Time</th> <th>Depth to water (mm)</th> </tr> </thead> <tbody> <tr> <td>10.21</td> <td>950 (after filling)</td> </tr> <tr> <td>10.40</td> <td>940</td> </tr> <tr> <td>10.52</td> <td>940</td> </tr> <tr> <td>11.06</td> <td>940</td> </tr> <tr> <td>11.17</td> <td>940</td> </tr> <tr> <td>11.24</td> <td>940</td> </tr> <tr> <td>11.39</td> <td>940</td> </tr> <tr> <td>12.07</td> <td>940</td> </tr> <tr> <td>13.35</td> <td>940</td> </tr> <tr> <td>14.00</td> <td>940</td> </tr> <tr> <td>15.05</td> <td>940</td> </tr> <tr> <td>16.00</td> <td>940</td> </tr> <tr> <td>16.34</td> <td>940</td> </tr> </tbody> </table>				Time	Depth to water (mm)	10.21	950 (after filling)	10.40	940	10.52	940	11.06	940	11.17	940	11.24	940	11.39	940	12.07	940	13.35	940	14.00	940	15.05	940	16.00	940	16.34	940
Time	Depth to water (mm)																																	
10.21	950 (after filling)																																	
10.40	940																																	
10.52	940																																	
11.06	940																																	
11.17	940																																	
11.24	940																																	
11.39	940																																	
12.07	940																																	
13.35	940																																	
14.00	940																																	
15.05	940																																	
16.00	940																																	
16.34	940																																	