

PLAZA CINEMA RE-DEVELOPMENT, PORT TALBOT

REMEDIATION VALIDATION ASSESSMENT REPORT

Report No. Q0045/VR

August 2022

DOCUMENT CONTROL

Contract Name: Plaza Cinema Re-Development, Port Talbot

Contract Reference: Q0045

Report Type: Remediation Validation Assessment Report

Report Reference: Q0045/VR

Date of Report Production: August 2022

Client: BAM Construction

Version:	Date:	Prepared by:	Checked by:	Approved by:
		L. Simlett	P. Darby	R. McDermott
Final Issue	19/08/22			
		Engineering Geologist B.Sc. (Hons), FGS	Chartered Senior Engineering Geologist B.Sc.(Hons), M.Sc., C.Geol., FGS	Managing Director Chartered Engineering Geologist B.Sc.(Hons), M.Sc., C.Geol., FGS, TechIOSH, NEBOSH

Disclaimer: Quantum Geotechnical Limited has prepared this report in accordance with the instructions of the above-named Client for their sole and specific use. Any third parties who may use the information contained herein do so at their own risk.

Quantum Geotechnic Ltd, Plas Newydd, Llanedi, Swansea, SA4 0FQ T: 01554 744880 E: enquiries@quantumgeotech.co.uk

CONTENTS

0.0	FOREWORD	3
1.0	INTRODUCTION	4
1.1	General	4
1.2	Aims & Objectives of Report	4
2.0	PAST STUDIES.....	5
2.1	Background.....	5
2.2	Overview of Past Studies.....	5
3.0	REMEDIATION STRATEGY.....	10
3.1	Derivation of Remediation Strategy & Recommended Actions	10
4.0	REMEDIATION VALIDATION	12
4.1	General	12
4.2	Elevated Shallow Ground Contamination: Measures Implemented	12
4.3	Elevated Shallow Ground Soil Leachate Contamination: Measures Implemented	13
4.4	Protection of Potable Water: Measures Implemented	13
5.0	CONFIRMATION OF VALIDATION AND VERIFICATION	14
6.0	REFERENCES	15

APPENDICES

APPENDIX I – SCHEME DRAWINGS & END SITE PHOTOGRAPHS	I
APPENDIX II – SITE PHOTOGRAPHS: EXCAVATION WORKS	II
APPENDIX III – WASTE TRANSFER SUMMARY RECORD & SAMPLED WTNS	III
APPENDIX IV – IMPORTED MATERIAL SUMMARY RECORD.....	IV

0.0 FOREWORD

The following Report is based on information gained from previous studies undertaken in relation to the site, supplemented by information and data provided by the Main Contractor in support of this Remediation Validation Assessment.

Quantum Geotechnic Ltd have provided the Main Contractor with Consultancy support during these works, relating to remediation procedures, quality control and evidence gathering guiding the Main Contractor to ensure that the Remediation Strategies for the works are adhered to and dutifully fulfilled. Where referenced, past studies in relation to the site should be read in conjunction with this Report.

1.0 INTRODUCTION

1.1 General

Upon the instructions of BAM Construction (the Client), Quantum Geotechnic Limited (QGL) has been commissioned to undertake a Validation and Verification exercise of the recently completed development of the disused Plaza Cinema site in Port Talbot into a proposed mixed-use building including renovation to the structure and external facings of the existing cinema building, commercial development internally and upgrade/ renovation of the external court yard areas to the rear, primarily for parking and bin storage.

This report is required as part of the Planning Conditions set out by the Local Planning Authority in relation to this development.

The following Report provides an overview of the risks previously identified in relation to contaminated land, the remedial strategy employed for the development and provides Validation and Verification that the Remedial Strategy has been adhered to through recorded documentation, drawings and photographic evidence during the construction works, supplemented by additional testing and verification where considered necessary to validate that any determined risks have been either removed or reduced to acceptable levels upon completion of the development.

1.2 Aims & Objectives of Report

To ensure that any Remedial Measures considered necessary for the development have been undertaken in accordance with the Remedial Strategy.

2.0 PAST STUDIES

2.1 Background

This former Plaza Cinema development has been subject to several past studies and assessments as part of the ongoing process of contaminated land risk identification and remediation process development. These past studies are listed in chronological order below and should be read in conjunction with this report to provide a comprehensive understanding and rationale behind the Conclusions herein;

1. *Proposed Development at The Plaza Cinema, Port Talbot, Ground Investigation Interpretative Report* Ref; Q0045/IR, Quantum Geotechnic Ltd, September 2019
2. *Proposed Development at The Plaza Cinema, Port Talbot, Remediation Strategy Report* Ref; Q0045/RS, Quantum Geotechnic Ltd, August 2020
3. *Technical Advice Note 01: Geotechnical Appraisal*, Ref; Q0045-TAN01, Quantum Geotechnic Ltd, 2nd July 2020
4. *Technical Advice Note 02: Ground Stabilisation*, Ref; Q0045-TAN02, Quantum Geotechnic Ltd, 6th November 2020

2.2 Overview of Past Studies

A synopsis of each report referenced above is provided below in Table 1.

Report Ref. #	Summary of Report & Findings
------------------	---------------------------------

This initial report was a combined Phase I Preliminary Risk Assessment (PRA) desk-based study and a Phase II Ground Investigation Interpretative Report. The Phase I PRA element of the report utilised information and data from existing information supplied by Neath Port Talbot County Borough Council (NPTCBC) via the Client. The PRA presented a conceptual site model for the development which identified potential contaminated land risks, albeit categorized as medium to high risk, notably;

1.
 - Possible made ground on-site from past re-profiling of the site and historic land use as railway lines in the northern area of the site.
 - Potential off-site contamination sources identified are the historic land-uses including the railway lines and tinsplate / steelworks. It is possible potential contamination from off-site sources will pose a risk to on site receptors from migration of soluble contaminants through the underlying Secondary A aquifer and windblown migration of dust/air borne contaminants. The risk from off-site land contamination is considered medium

Report Ref. #	Summary of Report & Findings
	The PRA recommended a ground investigation to sample the shallow soils and test for a range of potential contaminants to permit a human health risk assessment and environmental risk assessment to be undertaken and the revision of the Conceptual Site Models to determine if any unacceptable pollutant linkages exist. The Phase II Ground Investigation works detailed within this Report and undertaken in August 2019, included trial holes, both hand and machine excavated, in-situ soakaway testing and dynamic/ rotary cored boreholes located across the proposed development area, both internal to the existing Plaza Cinema building and in the external small courtyard area to the rear (north). A regime of contaminated land testing of soils, soil leachates and groundwater were undertaken, the results of which were used in a human health risk assessment and environmental assessment to identify unacceptable risks. Several potential Heavy Metal, Polycyclic Aromatic Hydrocarbons (PAH) and Total Petroleum Hydrocarbon (TPH) contaminants were recorded above the relevant Human Health Risk assessment criteria, notably published Soil Guideline Values (SGV) and Generic Assessment Criteria (GAC). Concentrations were compared against Residential without Plant Uptake scenario and against Commercial End Use scenario for completeness. The ground investigation revealed up to 2.2m of granular Made Ground material mantling the site external to the building whilst internally, the existing reinforced concrete slab rested directly onto natural soils. The Made Ground or Reinforced Concrete Slab were underlain by cohesive or granular alluvial fan deposits with bedrock residing between 6.8-7.8m below existing ground level. When comparing the chemical datasets against Residential End Use without plant uptake the following was determined: ▪ PAH derivatives Benzo(a)pyrene, Benzo(b)fluoranthene and Dibenzo(a,h)anthracene were at concentrations above the relevant assessment criteria within samples of Made Ground from BH1, BH2, TP1, HP2 and HP4; ▪ Benzo(a)anthracene was above the relevant assessment criteria within the samples of Made Ground from BH1, TP1, HP2 and HP4; ▪ Chrysene, Naphthalene and TPH Aromatic >EC16-21 banding were above the relevant assessment criteria within samples of Made Ground from BH2 and TP1; ▪ Nickel was at a concentration above the relevant assessment criteria within the sample of Made Ground from TP1 ▪ TPH Aromatic >EC12-16 and >EC21-35 bandings were above the relevant assessment criteria

Report Ref. #	Summary of Report & Findings
------------------	---------------------------------

within the sample of Made Ground from BH2.

Based on the above the raised contaminant concentrations were identified external to the Plaza building.

The laboratory chemical datasets were also assessed against Commercial End Use scenario criteria for completeness. The following was identified;

- Dibenz(a,h)anthracene concentrations within the Made Ground in BH2, TP1 and HP2 were above the relevant assessment criteria;
- Benzo(a)pyrene, Benzo(b)fluoranthene and Indeno(1,2,3-cd)pyrene were above the relevant assessment criteria in the Made Ground within BH2
- Nickel within the Made Ground within TP1 was above the relevant assessment criteria.

The concentrations of Semi-Volatile Organic Compounds (SVOC) and Volatile Organic Compounds (VOC) measured were all below the relevant assessment criteria for both residential and commercial land use.

Asbestos fibres were identified within samples of Made Ground obtained from BH2, TP1, HP2 and HP4. Quantification testing revealed the quantity within the samples from BH2, TP1 and HP4 to be <0.001% and therefore not considered to pose a risk to human health. The quantity measured within the sample from HP2 was 0.001% which is at the threshold level and may therefore pose a risk to human health albeit a very low risk.

No raised land gases or VOC gas vapours were recorded either during the Ground Investigation work or during post-fieldwork monitoring of installed standpipes.

Based on the comparisons between the measured potential contaminant concentrations and the relevant assessment criteria, the Made Ground present externally to the existing building across the site may pose a significant risk to human health of future proposed site users and should therefore be considered a potential contaminant source, and thereby a source-pathway-receptor linkage is realised within the Conceptual Site Model.

The risk to controlled waters including the underlying Secondary A aquifer was also assessed in the report through testing of soil leachates.

Leachate testing revealed raised concentrations of Copper and Zinc. Groundwater was revealed to reside below 2.40mbgl during the ground investigation works with subsequent water monitoring

Report Ref. #	Summary of Report & Findings
------------------	---------------------------------

recorded water at 0.94mbgl in BH1 location. Based on these results there is a potential for leachate generation from the Made Ground and thereby a risk to controlled waters. However, the report continues to state that given the extensile current and historical land uses in the area, it is likely that the impact of potential leachate generation containing Copper and/or raised Zinc values from the Made Ground on site on the underlying Secondary A aquifer is negligible. There are no surface water sources nearby and as such the risk to these is also considered negligible.

Based on the above, Remedial Measures were deemed necessary for the development in terms of the presence of contaminated land, the risks posed to human health and potential risks posed to the environment/ controlled waters.

The Remediation Strategy Report in August 2020 identified the five main risks as derived from the Ground Investigation findings which all related to raised contamination levels within the shallow lying Made Ground soils revealed across the site. The risks were detailed as raised contaminant levels above the Commercial End Use soil guideline values and/ or against . These were;

2.
 - **Risk 1:** Elevated Polycyclic Aromatic Hydrocarbons (PAH) in Soils to maximum depth of 0.50mbgl. Raised determinands were; Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Chrysene, Dibenz(a,h)anthracene, Indeno(1,2,3-cd) Pyrene and Naphthalene.
 - **Risk 2:** Elevated Heavy Metals in Soils to maximum depth of 0.30mbgl. Raised determinand was solely Nickel.
 - **Risk 3:** Elevated Total Petroleum Hydrocarbons (TPH) in Soils to maximum depth of 0.30mbgl. These elevated determinand were; TPH – Aromatic > EC12 – 16, TPH – Aromatic > EC16 – 21 and TPH – Aromatic > EC21 – 35
 - **Risk 4:** Elevated Heavy Metals within Soil Leachate test results compared to Environmental Quality Standards for freshwater. These elevated determinands were; Copper and Zinc
 - **Risk 5:** Risk to Potable Water. Due to the raised hydrocarbons in particular recorded within the soil analysis of the made ground material, there is a considered risk to potable water pipes through chemical attack if they were laid within the existing made ground.

This Remediation Strategy Report detailed the Remedial Measures to be adopted for each of the five risks and the development as a whole. In summary, Risks 1-4 would be built out during the development process, whilst Risk 5 would depend on the end design and whether alternate pipe material would be required such as barrier pipe. Details of the Remediation Strategy are presented in further detail within Section 3.0 within this Validation Report.

Report Ref. #	Summary of Report & Findings
------------------	---------------------------------

This Technical Advice Note (TAN 01) was solely related to geotechnical aspects of the scheme, to provide further ground information for foundation design. It involved a series of windowless sample boreholes and accompanying super heavy dynamic probes to derive shallow ground geotechnical design parameters primarily along the south-eastern elevation (Eagle Street) of the existing Plaza building.

3.

The findings of these additional boreholes and in-situ testing were presented under TAN01 dated 2nd July 2020.

This report did not contribute to, or result in, modification of the August 2020 Remediation Strategy Report.

Technical Advice Note (TAN 02), presented the findings of additional onsite trial pits, excavated to allow further assessment of shallow ground conditions and existing foundations of the Plaza building.

These additional works were required to inform any temporary works designs or remedial structural works in two areas: In relation to the south-west interface of the remaining structure and new build; and along the north-west elevation where the ground is to be lowered adjacent to an existing retaining wall.

4.

The intention in this latter area is to try and create a stable soil block behind the existing retaining wall that will alleviate the load on the wall in its current configuration when levels are reduced in front of it.

Technical Advice Note TAN02, dated 6th November 2020, presented the records of the three trial holes adjacent the building and concentrated on the ground conditions adjacent to the retaining wall on the north-western elevation of the site.

This report did not contribute to, or result in, modification of the August 2020 Remediation Strategy Report.

Table 1: Synopsis of Previous Studies of the Site

Based on the above, Remedial Measures were deemed necessary for the development in terms of the presence of contaminated land and contaminated land related issues.

3.0 REMEDIATION STRATEGY

3.1 Derivation of Remediation Strategy & Recommended Actions

The past study has revealed that remediation is required in relation to contaminated land and contaminated land related issues.

The revised Conceptual Site Model following the intrusive ground investigation and subsequent further testing based on the comparisons between the measured potential contaminant concentrations and the relevant assessment criteria concluded that the Made Ground present externally to the existing building across the site may pose a significant health risk to future site users for both residential and commercial land use and should therefore be considered a potential contaminant source unless remedial or protective measures are undertaken.

It is important to note that the development will entail keeping the existing building and undertaking structural and aesthetic renovation/ improvements.

The small hardstanding/ part gravel area to the rear (courtyard) of the building will be a mix of concrete hardstanding and paving. No soft landscaping is proposed as part of the development. If any planting is to be undertaken this will be in raised beds.

Risks 1 to 3 previously detailed will be mitigated through the construction process. The designs indicated that the existing footprint of the plaza building will be effectively maintained, albeit with partial demolition and re-build in the northern section. The building covers at least 80% of the site and therefore provides an effective 'capping', severing the potential pollutant linkage and pathway between site end users of the building and the identified elevated contaminants within the existing shallow made ground soils.

The remaining 20% footprint of the site is the external courtyard area in the northern end, which will be hardstanding and function as a car park, storage, delivery and service maintenance accessway. No soft landscaping is proposed. The hardstanding would also serve as a barrier between the made ground soils and site end users.

In relation to the raised soil leachate concentrations of Copper and Zinc, presented as Risk 4, this will also effectively be built out during the construction process. Post fieldwork groundwater sampling and subsequent laboratory testing was undertaken on groundwater samples obtained from BH1 and BH3, where the raised soil leachate results were previously recorded to a maximum depth of 1.0m. No potentially significantly elevated contaminants were measured within the groundwater samples tested. Therefore, although the Made Ground present across the site contains potentially mobile heavy metals, the groundwater test results indicate these potential contaminants are not significantly adversely affecting

groundwater quality below the site. Given the findings of the investigation, it is recommended no additional waters are introduced into the Made Ground deposits below the site (such as via soakaways) which may increase the potential for leachate generation.

The remaining Risk 5 was in relation to potable water supply to site. Due to the elevated hydrocarbons noted within Risks 1 and 3, here represented a risk, albeit low, to any newly installed potable water supply pipework. The Remediation Strategy Report recommended that either a full UKWIR assessment be undertaken to confirm the material type for any newly installed potable water feed or barrier pipework be adopted to prevent potential chemical attack and degradation of the water pipe material leading to contamination of the water supply.

4.0 REMEDIATION VALIDATION

4.1 General

The following section sets out remediation measures deemed necessary with associated evidential proof that have been implemented during the renovation and partial construction of the new Plaza building and overall site.

4.2 Elevated Shallow Ground Contamination: Measures Implemented

The end development did comprise the existing Plaza building being renovated, upgraded and marginally extended northwards and thereby covering approximately 80% of the entire site providing an effective barrier between site end users and the previously identified shallow lying made ground soils which exhibited elevated hydrocarbons and heavy metals.

Similarly, the remaining external area of the site at the rear, now comprises all concrete and block paving, utilised mainly as a car parking facility with storage area and general rear access to the building for maintenance. The only soft landscaping onsite is a corner of this rear courtyard area, measuring 1m wide by 3.5m in length and is effectively a raised bed with hardy shrubs.

Appendix I presents a series of scheme drawings showing the design detail of the end development, along with photographs of the finished development.

Whilst the building and hardstanding has nullified the risk from the previously recorded made ground, it is worth noting that as part of the development, the rear section of the original Plaza building was demolished and re-built. As part of this process, the site levels were significantly reduced, and all made ground soils were excavated and disposed of offsite. This was undertaken via construction sub-contractors, Darlow Lloyd Construction Ltd, with Neal Soil Suppliers Ltd the employed muck away/ haulage contractor.

The removal of the made ground soils was undertaken at intervals as the scheme progressed between October 2020 and March 2021. Up to 2,484.5 Tonnes of material was removed from the northern section of site, beneath the re-built northern building section and the rear courtyard area. This material was taken to Neal Soil Suppliers Ltd facility in Atlantic Wharf, Cardiff under waste classification EWC coding 17 05 04, non-hazardous waste soil.

Appendix II presents selected site photographic records of the earthworks period of the development as it progressed.

Appendix III is summary record of all the removed soil haulage loads along with sampled waste transfer

note (WTN) tickets. For ease of reporting, not all tickets are presented, there are 138 in total for record.

Following removal of the made ground/ shallow soils, and reduction of site levels, various imported clean engineering stone was laid to form the end formation. Approximately 920 Tonnes of stone was imported and laid across the site. This was supplied by Tarmac Aggregates and comprised mainly Type 1 sub-base, fine binding dust and graded limestone pipe bedding.

Appendix IV is a summary record of all imported material.

4.3 Elevated Shallow Ground Soil Leachate Contamination: Measures Implemented

Soil leachate testing recorded raised Copper and Zinc levels. However, subsequent groundwater sampling and testing did not reveal any raised contaminant levels and therefore any raised contaminants held within the made ground soils are considered immobile and unlikely to be leaching into the deeper lying natural soils and subsequently the groundwater. Nonetheless, what residual risk there may have been has been further removed by the excavation and removal of the made ground from site as part of the development as detailed in Section 4.2, and the hardstanding cover onsite has prevented stormwater directly infiltrating the soils.

4.4 Protection of Potable Water: Measures Implemented

The risk to newly installed potable water pipework was identified in the earlier ground investigation due to elevated hydrocarbons in the made ground. However, the subsequent removal of the made ground from site and replacement with imported stone has removed this risk. It is understood that only a 1.5m new section of potable water pipe was required to connect the existing line in the adjacent pavement along Eagle Street into the new building. The Client has confirmed that this short new section was placed in imported pipe bedding which itself was surrounded by the imported Type 1 stone. Therefore, no barrier pipe was required as the risk had been negated. Traditional PVC material pipework was used.

5.0 CONFIRMATION OF VALIDATION AND VERIFICATION

Section 4.0 detailed the remediation works required and subsequently undertaken.

Through documented evidence and records provided within this Report, Quantum Geotechnic Ltd consider that all Remediation Measures deemed as a requirement for the site have been implemented by the Client in line with the Remediation Strategies. The works have been verified by Quantum Geotechnic Ltd.

6.0 REFERENCES

Past Related Studies:

- *Proposed Development at The Plaza Cinema, Port Talbot, Ground Investigation Interpretative Report* Ref; Q0045/IR, Quantum Geotechnic Ltd, September 2019
- *Proposed Development at The Plaza Cinema, Port Talbot, Remediation Strategy Report* Ref; Q0045/RS, Quantum Geotechnic Ltd, August 2020
- *Technical Advice Note 01: Geotechnical Appraisal*, Ref; Q0045-TAN01, Quantum Geotechnic Ltd, 2nd July 2020
- *Technical Advice Note 02: Ground Stabilisation*, Ref; Q0045-TAN02, Quantum Geotechnic Ltd, 6th November 2020

Industry Guidance and Technical Publications:-

- British Code of Practice BS 5930:2015 +A1:2020 'Code of Practice for Site Investigations'
- British Code of Practice BS 1377:1990 'Methods of test for soils for civil engineering purposes'.
- British Code of Practice BS 10175:2011+A2:2017 'Code of Practice for Investigation of Potentially Contaminated Sites'
- British Code of Practice BS EN ISO 14688-1:2002+A2:2013 Geotechnical investigation and testing. Identification and classification of soil. Identification and description
- British Code of Practice BS EN ISO 14688-2:2004+A2:2013 Geotechnical investigation and testing. Identification and classification of soil. Principles for a classification.
- British Code of Practice BS EN ISO 14689-1:2003 Ground Investigation and Testing – Identification and classification of rock
- Health and Safety Executive Guidance Note EH40/90
- CIRIA Report 143 'The Standard Penetration Test (SPT): Methods and Use', 1995.
- BRE (2005) Special Digest 1:2005, 3rd Edition, Concrete in aggressive ground. BRE, Garston.
- BS 6031: 2009 Code of Practice for Earthworks.
- Workmanship for excavation shall comply with BS 8000: 1989 Part 1, Sections 3.1, 3.2 and 3.3.
- Specification for Highway Works (MCHW 1), Volume 1, Series 600 & Series 800, 2006 with Amendment 2016
- ICE UK Specification for Ground Investigation Second Edition.
- Design Manual for Roads and Bridges: Volume 7 Pavement Design and Maintenance
- Specification for Highways Works Series 600 Earthworks
- Highways Agency Interim Advice Note 73/06, Rev 1 2009, Clause 7.7
- Environmental Protection Act 1990: Part IIA Waste on Land
- Environment Act (1995). Section 57 Contaminated Land
- CIRIA Report C665 (2007) Assessing risks posed by hazardous gases to buildings.
- Environment Agency (2013) What's in your Backyard Online Mapping

- CIRIA Report C552 (2001) Contaminated Land Risk Assessment – A guide to good practice
- BS8485: 2007 Code of Practice for the Characterisation and Remediation from Ground Gas in Affected Developments

APPENDIX I – SCHEME DRAWINGS & END SITE PHOTOGRAPHS

This drawing is the property of GWP Architecture. Copyright is reserved by them and the drawing is issued on the condition that it is not copied, reproduced, retained, or disclosed to any unauthorised person, either wholly or in part, without the consent in writing of GWP Architecture.

All drawings and specifications should be read in conjunction with the project health and safety plan, any possible conflicts should be presented to the Planning Coordinator.

All work to be carried out in accordance with current Building Regulations.


Contractors must verify all dimensions at the job before commencing any work or making shop drawings.

Written dimensions should be taken.


Do not scale off drawing.

Do not take digital dimensions from this drawing.

Any discrepancies to be reported to the Architect.



Application site boundary



P02	28.05.19	update as per planning consultant's comments	CT	RT
P01	17.05.19	First Issue	CT	RT
Rev	Date	Comment	Dr	Ch




CHARTERED ARCHITECTS
INTERIOR DESIGNERS
SPACE PLANNERS
PROJECT MANAGERS
LANDSCAPE ARCHITECTS

15th Brunel House 2 Frazarion Road Cardiff CF24 0EB
+44(0)2921 303 322 (H) (R)Contact Fax (R)
architecture@gwp-arch.com | www.gwp-arch.com

.....
GWP Job Reference PPT

Job Title Plaza Port Talbot

Client
Neath Port Talbot County Borough Council



Name PPT-GWP-01-00-DR-A-(PA)-0001			
Scale	1:1250@A3	Revision	02
Drawn/Checked	CT/RT	First Issue	17.05.2019
Drawing Status	S - Work In Progress		

This drawing is the property of GWP Architecture. Copyright is reserved by them and the drawing is issued on the condition that it is not copied, reproduced, retained, or disclosed to any unauthorised person, either wholly or in part, without the consent in writing of GWP Architecture.

All drawings and specifications should be read in conjunction with the project health and safety plan, any possible conflicts should be presented to the Planning Coordinator.

All work to be carried out in accordance with current Building Regulations.


Contractors must verify all dimensions at the job before commencing any work or making shop drawings.

Written dimensions should be taken.

Do not scale off drawing.

Do not take digital dimensions from this drawing.

Any discrepancies to be reported to the Architect.



Existing Wall

Proposed New Wall

P10	10.09.19	Entrance doors opening shown. Reception position amended & digital studio reconfigured at client request	BP	RT
P09	10.07.19	Wall thickness updates.	DT	RT
P08	21.06.19	Reception box; lift shaft; room names updates.	DT	RT
P07	31.05.19	General Updates	DT	RT
Rev	Date	Comment	Dr	Ch



CHARTERED ARCHITECTS
INTERIOR DESIGNERS
SPACE PLANNERS
PROJECT MANAGERS
LANDSCAPE ARCHITECTS

15th Brunel House 2 Frazar Road Cardiff CF24 0EB
+44(0)2921 303 322 (H) (F)Contact Fax (F)
architecture@gwp-arch.com | www.gwp-arch.com

GWP Job Reference PPT

Job Title Plaza Port Talbot

Client
Neath Port Talbot County
Borough Council


Proposed Ground Floor GA Plan

Name PPT-GWP-01-GF-DR-A-(PA)-0031

Scale	1:200@A3	Revision	10
Drawn/Checked	DT/RT	First Issue	01.05.2019
Drawing Status	S - Work In Progress		

B:\McCloud - BIM\Server\HP - BIM\Cloud Basic for ARCHICAD 22\138511902-GWP-01-XX-W3-A-18-PortTalbot-P01

PROPOSED GROUND FLOOR PLAN
Scale 1:200



PROPOSED ROOF PLAN
Scale 1:200

This drawing is the property of GWP Architecture. Copyright is reserved by them and the drawing is issued on the condition that it is not copied, reproduced, retained, or disclosed to any unauthorised person, either wholly or in part, without the consent in writing of GWP Architecture.

All drawings and specifications should be read in conjunction with the project health and safety plan, any possible conflicts should be presented to the Planning Coordinator.

All work to be carried out in accordance with current Building Regulations.


Contractors must verify all dimensions at the job before commencing any work or making shop drawings.

Written dimensions should be taken.

Do not scale off drawing.

Do not take digital dimensions from this drawing.

Any discrepancies to be reported to the Architect.



- Green Roof
- Solar panel
- Plant Area
- Access Walkway
- New membrane roof to ex-surfaces
- Proposed rain water pipe to underground network (size TBC)
- Existing cast iron rain water pipe, refurbish + repair as necessary and repaint

P10	10.09.19	Roof access amended at client request	DT	RT
P09	25.07.19	Key updated	DT	RT
P08	18.07.19	Updated position of plant louvres	CT	RT
P07	10.07.19	General Updates	DT	RT
P06	21.06.19	General Updates	UKD	RT
P05	31.05.19	General Updates	DT	RT
P04	28.05.19	update as per planning consultant's comments	CT	RT
Rev	Date	Comment	Dr	Ch

GWPA

CHARTERED ARCHITECTS
INTERIOR DESIGNERS
SPACE PLANNERS
PROJECT MANAGERS
LANDSCAPE ARCHITECTS

15th Brunel House 2 Frazarion Road Cardiff CF24 0EB
+44(0)2921 303 322 (H) (R) Contact Fax (R)
architecture@gwp-arch.com | www.gwp-arch.com

..... PPT

GWP Job Reference

Job Title Plaza Port Talbot

Client
Neath Port Talbot County Borough Council

Proposed Roof GA Plan

Name	PPT-GWP-01-03-DR-A-(PA)-0034		
Scale	1:200@A3	Revision	10
Drawn/Checked	DT/RT	First Issue	01.05.2019
Drawing Status	S - Work In Progress		

BIMcloud: BIMServer-HP - BIMcloud Basic for ARCHICAD 22/138511902-GWP-01-XX-W3-A-18-PortTalbot-P01

This drawing is the property of GWP Architecture. Copyright is reserved by them and the drawing is issued on the condition that it is not copied, reproduced, retained, or disclosed to any unauthorised person, either wholly or in part, without the consent in writing of GWP Architecture.

All drawings and specifications should be read in conjunction with the project health and safety plan, any possible conflicts should be presented to the Planning Coordinator.

All work to be carried out in accordance with current Building Regulations.


Contractors must verify all dimensions at the job before commencing any work or making shop drawings.

Written dimensions should be taken.

Do not scale off drawing.

Do not take digital dimensions from this drawing.


Any discrepancies to be reported to the Architect.




Note
Section taken from James & Nicholas
(drawing reference):
Job No 12:15 - Drawing No A05
Plaza Cinema, Port Talbot - Existing Building
Elevations.

KEY

 Element to be demolished



EXISTING SOUTH ELEVATION
Scale 1:200



EXISTING WEST ELEVATION
Scale 1:200

P01	27.06.19	First Issue	DT	RT
Rev	Date	Comment	Dr	Ch



CHARTERED ARCHITECTS
INTERIOR DESIGNERS
SPACE PLANNERS
PROJECT MANAGERS
LANDSCAPE ARCHITECTS

15th Brunel House 2 Ffrizon Road Cardiff CF24 0EB
+44(0)2921 303 322 (H) #Contact Fax (R)
architecture@gwp-arch.com | www.gwp-arch.com

..... PPT

GWP Job Reference

Job Title Plaza Port Talbot

Client
Neath Port Talbot County
Borough Council

Demolition Elevations (South & West)

Name PPT-GWP-01-XX-DR-A-(PA)-0024			
Scale	1:200@A3	Revision	01
Drawn/Checked	DT/RT	First Issue	27.06.2019
Drawing Status S - Work In Progress			

Contract : Plaza Cinema, Port Talbot

Client : BAM Construction Ltd

Dates : 18/6/20 - 19/8/22

Location : Port Talbot

Job Number : Q0045

Engineer : Quantum Geotechnic



Photo 1: Completed Development - Front Elevation



Photo 2: Completed Development - East Elevation (Eagle Street)

Contract : Plaza Cinema, Port Talbot

Client : BAM Construction Ltd

Dates : 18/6/20 - 19/8/22

Location : Port Talbot

Job Number : Q0045

Engineer : Quantum Geotechnic



Photo 3: Completed Development - Southern Elevation



Photo 4: Completed Development - South and Western Elevations (incl. courtyard area)

APPENDIX II – SITE PHOTOGRAPHS: EXCAVATION WORKS

Contract : Plaza Cinema, Port Talbot

Client : BAM Construction Ltd

Dates : 18/6/20 - 19/8/22

Location : Port Talbot

Job Number : Q0045

Engineer : Quantum Geotechnic



Photo 1: Demolition of northern end of existing Plaza building



Photo 2: Reduced dig of existing soils & demolition stockpile for screening, crushing and offsite disposal

Contract : Plaza Cinema, Port Talbot

Client : BAM Construction Ltd

Dates : 18/6/20 - 19/8/22

Location : Port Talbot

Job Number : Q0045

Engineer : Quantum Geotechnic



Photo 3: Reduced dig ongoing and removal offsite



Photo 4: Reduced dig ongoing, offsite disposal (Neals) and laying of imported stone

Contract : Plaza Cinema, Port Talbot

Client : BAM Construction Ltd

Dates : 18/6/20 - 19/8/22

Location : Port Talbot

Job Number : Q0045

Engineer : Quantum Geotechnic



Photo 5: Levels being brought up using imported engineered stone



Photo 6: New foundations in place for the rebuild of northern Plaza building section

Contract : Plaza Cinema, Port Talbot

Client : BAM Construction Ltd

Dates :

Location : Port Talbot

Job Number : Q0045

Engineer : Quantum Geotechnic



Photo 7: Formation back up to level ready for construction of building section and courtyard area top of photo.

APPENDIX III – WASTE TRANSFER SUMMARY RECORD & SAMPLED WTNS

NEAL
SOIL SUPPLIES LTD

[illegible]

	5124
	2,484.50
TOTAL TONNAGE	



Atlantic Eco Park, Newton Road, Rummy, Cardiff CF3 2EJ
Longships Road, Cardiff Docks, Cardiff CF10 4LU
Tel: 029 2079 7835 Fax: 029 2036 0043

EA Site Permit: EPR/VP3095FS
EA Site Permit: EPR/UP3398EK

Duty of Care - Waste Transfer / Delivery Note

Date 29/10/2020

Job Number: 487366

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7908), Plaza Cinema, Bem
Offices (Eagles House), Talbot Rd,
Port Talbot, SA13 1DH

SIC Code

Order Details

HIAJ

ECM7908

PO

Grade & EWC

Non Hazardous Soil & Stone - (17 05 04)
- 17 05 04

I confirm that I have fulfilled my duty to apply
the waste hierarchy as required by Regulation
12 of the Waste (England and Wales)
Regulations 2011.

Customer Signature

Print Name

Time on Site

Time Off Site

[Handwritten Signature]

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number

CBDU2877 yd11f60

Signed

Vehicle Reg

MJ PLANT

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rummy, Cardiff, CF3
2EJ

EA Registration Number

EPR/VP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY

VAT Reg. No. 691 9081 06



Your Waste Partner

PRODUCERS CERTIFICATE (See conditions overhead)

Company No. 3368496

Description of Waste: Where waste is discovered to be
inconsistent with the description by the Customer or their agent,
the owner reserves the right to recover the appropriate charges
and associated tax, together with other costs incurred.



Atlantic Eco Park, Newton Road, Rummy, Cardiff CF3 2EJ
Longships Road, Cardiff Docks, Cardiff CF10 4LU
Tel: 029 2070 7835 Fax: 029 2036 0043

EA Site Permit: EPR/VP3095FS
EA Site Permit: EPR/UP3396EK

Duty of Care - Waste Transfer / Delivery Note

Date 29/10/2020

Job Number: 487357

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7908), Plaza Cinema, Bam
Offices (Eagles House), Talbot Rd,
Port Talbot, SA13 1DH

I confirm that I have fulfilled my duty to apply
the waste hierarchy as required by Regulation
12 of the Waste (England and Wales)
Regulations 2011.

Customer Signature

Print Name

Time on Site Time Off Site

SIC Code

Order Details

HAU

PO ECM7908

Grade & EWC

Non Hazardous Soil & Stone - (17 05 04)
17 05 04

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number

CBDU2077

Signed

Vehicle Reg

S. MURPHY

WJ PLANT

KM15 GGE

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rummy, Cardiff, CF3
2EJ

EA Registration Number

EPR/VP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY

VAT Reg. No. 691 9081 06



Your Waste Partner

PRODUCERS CERTIFICATE (see conditions overleaf)

Company No. 3368495

Description of Waste: Where waste is discovered to be
inconsistent with the description by the Customer or their agent,
the owner reserves the right to recover the appropriate charges
and associated tax, together with other costs incurred.



Atlantic Eco Park, Newton Road, Rumney, Cardiff CF3 2EJ
Longships Road, Cardiff Docks, Cardiff CF10 4LU
Tel: 029 2078 7835 Fax: 029 2036 0043

EA Site Permit: EPR/VP3095FS
EA Site Permit: EPR/UP3398EK

Duty of Care - Waste Transfer / Delivery Note

Date 29/10/2020

Job Number: 487368

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7808), Plaza Cinema, Barn
Offices (Eagles House), Talbot Rd,
Port Talbot, SA13 1DH

SIC Code

Order Details

HAU

PO ECM7808

Code & EWC

Non Hazardous Soil & Stone - (17 05 04)
- 17 05 04

I confirm that I have fulfilled my duty to apply
the waste hierarchy as required by Regulation
12 of the Waste (England and Wales)
Regulations 2011.

Customer Signature

Print Name

Time on Site

Time Off Site

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number
CBDU2977

Signed

Vehicle Reg

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rumney, Cardiff, CF3
2EJ

EA Registration Number
EPR/VP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY

VAT Reg. No. 691 9081 06



Your Waste Partner

PRODUCERS CERTIFICATE (See conditions overleaf)

Company No. 3369495

Description of Waste: Where waste is discovered to be
inconsistent with the description by the Customer or their agent,
the owner reserves the right to recover the appropriate charges
and associated tax, together with other costs incurred.



Atlantic Eco Park, Newton Road, Rumney, Cardiff CF3 2EJ
Longships Road, Cardiff Docks, Cardiff CF10 4LU
Tel: 029 2079 7835 Fax: 029 2036 0043

EA Site Permit: EPR/VP3095FS
EA Site Permit: EPR/UP3398EK

Duty of Care - Waste Transfer / Delivery Note

Date 29/10/2020

Job Number: 487360

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7908), Plaza Cinema, Bann
Offices (Excess House), Talbot Rd,
Port Talbot, SA13 1DH

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number

CBDU2977

SIC Code

Order Details

HAU

PO ECM7908

Code & EWC

Non Hazardous Soil & Stone - (17 05 04)
- 17 05 04

Signed

Vehicle Reg

MJ PLANT

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rumney, Cardiff, CF3
2EJ

EA Registration Number

EPR/VP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY

VAT Reg. No. 691 9081 06



Your Waste Partner

PRODUCERS CERTIFICATE (See conditions overleaf)

Company No. 3368495

Description of Waste: Where waste is discovered to be inconsistent with the description by the Customer or their agent, the owner reserves the right to recover the appropriate charges and associated tax, together with other costs incurred.



Atlantic Eco Park, Newton Road, Rumney, Cardiff CF3 2EJ
Longships Road, Cardiff Docks, Cardiff CF10 4LU
Tel: 029 2079 7835 Fax: 029 2036 0043

EA Site Permit: EPR/NP3095FS
EA Site Permit: EPR/UP3398EK

Duty of Care - Waste Transfer / Delivery Note

Date 23/11/2020

Job Number: 483064

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7908), Plaza Cinema, Barn
Offices (Eagles House), Talbot Rd,
Port Talbot, SA13 1DH

I confirm that I have fulfilled my duty to apply the waste hierarchy as required by Regulation 12 of the Waste (England and Wales) Regulations 2011.

Customer Signature 

Print Name _____

Time on Site _____ Time Off Site _____

SIC Code

Order Details
HAU

PO ECM7908

Grade & EWC

Non Hazardous Soil & Stone - (17 05 04)
- 17 05 04

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number

CB0U2977


Signed

Vehicle Reg MJ PLANT
KM15 GGC

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rumney, Cardiff, CF3
2EJ

EA Registration Number

EPR/NP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY

VAT Reg. No. 691 9081 06



PRODUCERS CERTIFICATE (See conditions overleaf)
Company No. 3368495

Description of Waste: Where waste is discovered to be inconsistent with the description by the Customer or their agent, the owner reserves the right to recover the appropriate charges and associated tax, together with other costs incurred.

Duty of Care - Waste Transfer / Delivery Note

Date 23/11/2020

Job Number: 403063

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7908), Plaza Cinema, Bann
Offices (Eagles House), Talbot Rd,
Port Talbot, SA13 1DH

I confirm that I have fulfilled my duty to apply
the waste hierarchy as required by Regulation
12 of the Waste (England and Wales)
Regulations 2011.

Customer Signature

Print Name

Time on Site

Time Off Site

SIC Code

Order Details

HAU

PO ECM7908

Grade & EWC

Non Hazardous Soil & Stone - (17 05 04)
- 17 05 04

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number

CBDU2977

Signed

Vehicle Reg

MJ PLANT
KM15 GGE

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rumney, Cardiff, CF3
2EJ

EA Registration Number

EPR/VP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY

VAT Reg. No. 601 9081 06



Your Waste Partner

PRODUCERS CERTIFICATE (See conditions overleaf)
Company No. 3068495

Description of Waste: Where waste is discovered to be
inconsistent with the description by the Customer or their agent,
the owner reserves the right to recover the appropriate charges
and associated tax, together with other costs incurred.



Atlantic Eco Park, Newton Road, Rumney, Cardiff CF3 2EJ
Longships Road, Cardiff Docks, Cardiff CF10 4LU
Tel: 029 2079 7835 Fax: 029 2036 0043

EA Site Permit: EPR/VP3095FS
EA Site Permit: EPR/UP3396EK

Duty of Care - Waste Transfer / Delivery Note

Date 27/11/2020

Job Number: 404376

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7908), Plaza Cinema, Bank
Offices (Eagles House), Talbot Rd,
Port Talbot, SA13 1DH

I confirm that I have fulfilled my duty to apply
the waste hierarchy as required by Regulation
12 of the Waste (England and Wales)
Regulations 2011.

Customer Signature

Print Name

Time on Site Time Off Site

SIC Code

Order Details

HAU

PO ECM7908

Grade & EWC

Non Hazardous Soil & Stone - (17 05 04)
- 17 05 04

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number

CB0DU2977

Signed

Vehicle Reg CE69 AZF

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rumney, Cardiff, CF3
2EJ

EA Registration Number

EPR/VP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY



Your Waste Partner

PRODUCERS CERTIFICATE (See conditions overleaf)

VAT Reg. No. 891 9087 06

Company No. 3388495

Description of Waste: Where waste is discovered to be
inconsistent with the description by the Customer or their agent,
the owner reserves the right to recover the appropriate charges
and associated tax, together with other costs incurred.

Duty of Care - Waste Transfer / Delivery Note

Date 27/11/2020

Job Number: 494375

Customer/Waste Producer

DARLOW LLOYD CONSTRUCTION
(ECM7908), Plaza Cinema, Barn
Offices (Eagles House), Talbot Rd,
Port Talbot, SA13 1DH

I confirm that I have fulfilled my duty to apply
the waste hierarchy as required by Regulation
12 of the Waste (England and Wales)
Regulations 2011.

Customer Signature

Print Name

Time on Site

Time Off Site

SIC Code

Order Details

HAU

PO

ECM7908

Grade & EWC

Non Hazardous Soil & Stone - (17 05 04)
- 17 05 04

Waste Carrier

NEAL SOIL SUPPLIERS LTD

EA Registration Number

C8DU2977

Signed

Vehicle Reg CE60 AZB

Waste/Product Receiver

NEAL SOIL SUPPLIERS LTD

Atlantic Eco Park, Newton
Road, Rummey, Cardiff, CF3
2EJ

EA Registration Number

EPR/VP3095FS

Signed

Notes

LEGAL LEVEL LOAD ONLY

VAT Reg. No. 681 9061 06



Your Waste Partner

PRODUCERS CERTIFICATE (See conditions overleaf)

Company No. 3358495

Description of Waste: Where waste is discovered to be
inconsistent with the description by the Customer or their agent,
the owner reserves the right to recover the appropriate charges
and associated tax, together with other costs incurred.

APPENDIX IV – IMPORTED MATERIAL SUMMARY RECORD

Ticket Date	Plant	Quote	Description	Quantity	Ticket number	Customer name	Ship-to street	Ship-to city
26/11/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.66	1202311567	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
26/11/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.64	1202311821	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
26/11/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.56	1202312092	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
27/11/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.9	1202316174	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
27/11/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.78	1202316458	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/12/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.5	1202323792	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/12/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.74	1202324321	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/12/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	20.02	1202324747	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/12/2020	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.8	1202326875	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
14/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.86	1202422449	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
14/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.7	1202422843	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
14/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.76	1202422906	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
15/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	20	1202425445	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
15/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.66	1202425885	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
22/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.56	1202446504	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
22/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.34	1202446516	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
22/01/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.9	1202446572	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/02/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.48	1202473436	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/02/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.66	1202473541	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/02/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.84	1202473553	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
01/02/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.74	1202473748	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
26/08/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.7	1203169764	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
26/08/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	15.12	1203172111	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
05/10/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.7	1203297003	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
08/10/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.74	1203311762	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
14/10/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.76	1203328950	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
23/11/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.52	1203470914	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
10/12/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	10.02	1203531879	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
16/12/2021	B211	1006396423	TYPE 1 SUB-BASE CL803 BF SLAG	19.3	1203553786	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
21/04/2021	B206	1006396423	TYPE 1 SUB-BASE CL803	19.54	1202744041	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
21/04/2021	B206	1006396423	TYPE 1 SUB-BASE CL803	19.46	1202744057	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
05/01/2021	B206	1006396423	0/4MM CFA LIMESTONE	19.14	1202397568	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
22/01/2021	B206	1006396423	0/4MM CFA LIMESTONE	9.88	1202449455	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
23/11/2021	B206	1006396423	0/4MM CFA LIMESTONE	10.2	1203471236	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
10/12/2021	B206	1006396423	0/4MM CFA LIMESTONE	9.9	1203530659	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
16/12/2021	B206	1006396423	0/4MM CFA LIMESTONE	10.24	1203551798	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
17/02/2022	B206	1006396423	ULTIFLOW 2/6MM LAYING COURSE	19.42	1203702719	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
17/02/2022	B206	1006396423	ULTIFLOW 2/6MM LAYING COURSE	15.1	1203703049	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
09/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.62	1203678820	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
09/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.66	1203678844	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
09/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.4	1203678959	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
09/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.4	1203678974	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
10/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.48	1203683824	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
10/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.5	1203684089	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
11/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	15.5	1203684902	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
11/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.74	1203684986	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
11/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.36	1203686938	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
14/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.38	1203689690	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
16/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.5	1203698467	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT
16/02/2022	B200	1006396423	10/63MM GRADED LIMESTONE	19.6	1203699832	DARLOW LLOYD (CONSTRUCTION) LTD	TALBOT ROAD	PORT TALBOT



Quantum Geotechnic Ltd
Plas Newydd
Pontardulais
Swansea
SA4 0FQ

T: 01554 744880
E: enquiries@quantumgeotech.co.uk
W: <http://www.quantumgeotech.co.uk>