

NOTES

Key

Red line boundary

Contour levels related to OS Datum

Temporary bund's to protect river Neath waters [to be installed and taken away on completion of works]

Existing Fencing Gates
All existing fencing and gates maintained during the contact to remain and handed back to site owners/LA on completion

Existing conveyor structures to be taken down, with steel work/sheeting at fittings/fixtures taken off site [demolition to be to top of foundation/slab level;- structures with flash to slab]

1. Recycling/restoration works machinery, conveyor, hopper. All structures above grand inc concrete, masonry, suspended slab carefully demolished and stock piled and crushed to 6F/2 dpt/WO highly specification
2. Crushed 6F2 material to be retained on site and used to infill ponds, lagoons and low areas

A Sep'22 Planning Approval RC
REV DATE Red Line Boundary BY CHKD
Added

CLIENT
Blue Rock LTD

PROJECT
Unity Mine Cwmgrach Neath

TITLE
Proposed Restoration Plan [June 2022]
[Overall Site]

GENERAL NOTES
A- The scale shown on this drawing only applies to the correct paper size.
B- Do not scale from this drawing take figured dimensions only.
C- Any discrepancies to be reported to ateb consult.
D- Drawings in PDF format are not to scale and are for reference only.

DATE 10/06/2022 PRODUCED BY E.PEET
SCALE 1:1000 CHECKED
PAPER SIZE A1 APPROVED

ateb Consult
42 Gurnos Road
Ystalyfera
Swansea
SA9 2HY
Tel: 01639 849279
Fax: 01639 849984
E-mail: info@atebconsult.co.uk

JOB NUMBER DRAWING NUMBER REVISION
22/041 101 A

