

NOTES

Existing Fencing Gates
All existing fencing and gates maintained during the contact to remain and handed back to site owners/LA on completion

Existing conveyor structures to be taken down, with steel work/sheeting at fittings/fixtures taken off site [demolition to be to top of foundation/slab level;- structures with flash to slab]

1. Recycling/restoration works machinery, conveyor, hopper. All structures above grand inc concrete, masonry, suspended slab carefully demolished and stock piled and crushed to 6F/2 dpt/WO highly specification
2. Crushed 6F2 material to be retained on site and used to infill ponds, lagoons and low areas

Existing gully's and pipes taking surface water to be broken out

1. Ex concrete lined lagoon L3 holding contaminated water/oils to be maintained

Existing culvert inspected and cleaned

Culvert grills and headwalls to be inspected, made good and retained

Ex overflow pipes between reserve/lagoon maintained

500mm earth boundary

Existing secondary sheds and storage building and contours all demolished to slab level

Existing railway lines to be protected where necessary and to remain

- Land Restoration Specification
1. Buildings demolished to site level
 2. Ground graded through to create even profile between track area of refilled area
 3. Area to be reprofiled from SW to NE direction

Drg depressed area L4 infilled to ex ground contour levels

Ex slab to be scraped, cleaned and to remain

Ex weigh bridge to be retained

Offices and canteen/lamp room and coal facilities demolished to top of ex slab level

Former stock pile/yard area cleared of waste/metal/rubbish/inert waste to ex ground level

Provide open grip drainage 300mm deep designed in herringbone fashion to guide storm/surface water runoff off hard areas

Existing dry [at July22] lagoon ref H1 to be backfilled with crushed material and surplus stockpiled material up to existing ground level contours

Hardstanding/ground to be cleared and profiled

All Cwmgrach Rail Lead linen to be protected during restoration works an to remain

Tributary connecting unity mine to river neath

Ex stream course to be maintained during works and left in clear condition

Provide bypass interceptor

Aftercare Provision
Aftercare provisions following planned clearance and restoration works to be provided by local authority

Stock Proof Fencing
Any post land reclamation stock proof fencing to be provided by others on contract completion

REV	DATE	BY	CHKD
-----	------	----	------

CLIENT
Blue Rock LTD

PROJECT
Unity Mine Cwmgrach Neath

TITLE
Proposed Bund & Site Boundary

GENERAL NOTES
A- The scale shown on this drawing only applies to the correct paper size.
B- Do not scale from this drawing take figured dimensions only.
C- Any discrepancies to be reported to ateb consult.
D- Drawings in PDF format are not to scale and are for reference only.

DATE 10/06/2022	PRODUCED BY R.Collier
SCALE 1:1000	CHECKED
PAPER SIZE A1	APPROVED

ateb Consult
42 Gurnos Road
Ystalyfera
Swansea
SA9 2HY
Tel: 01639 849279
Fax: 01639 849984
E-mail: info@atebconsult.co.uk

JOB NUMBER	DRAWING NUMBER	REVISION
22/041	500	—

