

Caution: This email originated from outside of the organisation. Do not click links or open attachments unless you recognise the sender and know the content is safe. If in doubt, contact the IT Service Desk

Morning Rhodri,

Please see answers to your queries below.

- ☐ The steps will be concrete with the goings are risers specified on the drawing.
- ☐ The existing ground profile roughly matches the staircase' gradient – there will be minimal local reprofiling required on both sides of the steps.
- ☐ Once the works are complete, the bank will be reinstated.
- ☐ To prevent erosion and help stabilise the bank after excavations, a pre-seeded hessian matting will be used in vicinity of steps / headwall structure. The matting will be pre-seeded with grass.
- ☐ There are no additional retaining walls required for the steps - these will be supported by the headwall slab, which is piled.

I hope this answers your queries. Should you have any further questions, please do not hesitate to contact me.

Kind regards,