



Foul Drainage Strategy subject to further consultation with DCWW. SuDS strategy subject to consultation with NPT SAB.

KEY

- Highway Rain Garden
- Highway Rain Garden Infiltration & high-level overflow
- Plot Rain Garden
- Porous Surface Finish (Infiltration) (Non-adoptable)
- Storm Drain (SAB Adoptable)
- Foul Sewer (S104 Adoptable)
- Storm Drain (Non-Adoptable)
- Carriageway Runoff Conveyance
- Orifice Control Chamber

INFILTRATION TESTING

Infiltration Testing undertaken February 2024 provided the following results:

TP01 - 1.45×10^{-5}
TP02 - 5.28×10^{-6}
TP03 - 9.21×10^{-6}
TP04 - 6.00×10^{-6}
TP05 - 2.18×10^{-5}