
NOTES

1. This drawing shall be read in conjunction with the civil engineering specification and all relevant Engineer's drawings.
2. This document must not be altered, reproduced or distributed without prior written consent of the originator.
3. Do not scale from this document – use figured dimensions only. All dimensions must be checked on site prior to commencement of any related works.
4. Any drawing error to be brought to the attention of the project manager before any works are undertaken.
5. The contract is made of the following risks associated with the works:
   - The presence of above and below ground services and structures, such apparatus may be live and form part of service critical infrastructure. The contractor is to locate, identify and secure all apparatus prior to undertaking any work. If discovered an appropriate management plan/risk assessment is to be submitted to the client for approval.
   - Appropriate tests are to be carried out on soils at sufficient intervals and depth to identify any contaminants that may impact on the h&s of operatives or the works. If discovered an appropriate management plan/risk assessment is to be submitted to the client for approval.
   - Heavy plant and rail freight operate across the site, the contractor is to agree with the client an appropriate management plan/risk assessment to protect the workforce.
   - Tests to identify the presence of tar bound materials in road surfacing materials are to be undertaken prior to any excavation in the material. If discovered an appropriate management plan/risk assessment is to be submitted to the client for approval.
   - The presence of harmful leachate and/or gas in excavations is to be identified and an appropriate management plan/risk assessment is to be submitted to the client for approval.
   - Existing ground conditions vary, the stability of any embankment or cutting and the baring capacity of the ground where loaded is to be assessed for suitability prior to works being carried out and an appropriate management plan/risk assessment is to be submitted to the client for approval.
   - The presence of unexploded ordnance should be anticipated, a magnetometer survey is to be undertaken prior to any works commencing to search for any unexploded ordnance, during the works a watching brief is to me kept to identify any potential materials that may represent a hazard to the workforce or completed scheme.

N


SCRAP YARD 2
SCRAP YARD POWER HOUSING
SCRAP YARD 1
MAIN COMPRESSOR HOUSING
NATIONAL GRID AREA OF RESPONSIBILITY
LOWER MOTHER DITCH
HARSCO SHREDDER AREA
OVERFLOW SCRAP STORAGE AREA
SWITCH ROOM
SKIP
SKIP
SKIP