



NODE	EASTING	NORTHING	COVER LEVEL	INVERT LEVEL	DEPTH TO SOFFIT	SUMP DEPTH	INCOMING DIAMETER	OUTGOING DIAMETER	COVER TYPE	M.H. TYPE + INTERNAL DIA.	REMARKS
SW.01	-	-	13.600	12.900	0.600	-	100	100	B125	TYPE 3 + 600	-
SW.02	-	-	13.500	12.800	0.600	-	100	100	B125	TYPE 3 + 600	-
SW.03	-	-	13.500	12.720	0.680	-	100	100	B125	TYPE 3 + 600	-

SURFACE WATER MANHOLE SCHEDULE

NODE	EASTING	NORTHING	COVER LEVEL	INVERT LEVEL	DEPTH TO SOFFIT	SUMP DEPTH	INCOMING DIAMETER	OUTGOING DIAMETER	COVER TYPE	M.H. TYPE + INTERNAL DIA.	REMARKS
FW.01	-	-	13.450	12.825	0.475	-	100	150	B125	TYPE 3 + 600	BUILT OVER EXISTING 100mm DIA. PIPE - INVERT LEVEL T.B.C ON SITE
FW.02	-	-	13.450	12.570	0.730	-	150	150	B125	TYPE 3 + 600	-
FW.03	-	-	13.500	12.455	0.895	-	150	150	B125	TYPE 3 + 600	-
SW.04	-	-	13.475	12.350	0.975	-	150	150	D400	TYPE 3 + 600	-
SW.05	-	-	13.475	12.575	0.750	-	150	150	B125	TYPE 3 + 600	BUILT OVER EXISTING 150mm DIA. PIPE - INVERT LEVEL T.B.C ON SITE - DRAINAGE DIVERSION TO BE APPROVED BY DCWW.
SW.06	-	-	13.475	12.360	0.965	-	150	150	B125	TYPE 3 + 600	DRAINAGE DIVERSION TO BE APPROVED BY DCWW.
SW.07	-	-	13.475	12.250	1.075	-	150	150	B125	TYPE 3 + 600	BUILT OVER EXISTING 150mm DIA. PIPE - INVERT LEVEL T.B.C ON SITE - DRAINAGE DIVERSION TO BE APPROVED BY DCWW.

FOUL WATER MANHOLE SCHEDULE

P1	10.09.25	JJD	RIBA Stage 3 Issue.
REV.	DATE	DRAWN	REVISION
DRAWING ISSUE STATUS			
☒ PRELIMINARY ISSUE ☐ TENDER ISSUE ☐ CONSTRUCTION ISSUE ☐ DESIGN DEVELOPMENT PRIOR TO TENDER ☐ DESIGN DEVELOPMENT PRIOR TO CONSTRUCTION ☐ AS BUILT ISSUE			
Austin Partnership Civil & Structural Engineering Consultants 11 Drake Walk, Waterfront 2000, Atlantic Wharf, Cardiff. CF10 4AN Tel: 029 2043 5300 Fax: 029 2043 5310 email: mail@austinpartnership.co.uk www.austinpartnership.co.uk			
CLIENT : Tilbury Douglas			
PROJECT : EDUCATION LIBRARY & RESOURCE CENTRE			
TITLE : MANHOLE SCHEDULES			
DATE : AUG. 2025		DRAWN : JJD	CHECKED : AS
SCALE : 1:1 @ A1			
PROJECT:	ORIGIN:	ZONE:	LEVEL:
100654	AUS	XX	XX
		TYPE:	ROLE:
		D	C
NUMBER:	CODE:	REV:	
1009	S1	P1	