

existing side elevation ne



existing side elevation sw



proposed side elevation ne



existing section

existing rear elevation nw

BRIEF ELECTRICS

All new electrical works are to be carried out under the Competent Persons Scheme supply and fix mains powered smoke detector alarms one to each floor interconnected and with battery backup.
Supply and fix mains operated mechanical extract fan to kitchen Elta Elair 6040 or similar approved giving 60 lit/sec. output.
Supply and fix mains operated mechanical extract fan to Utility Room Elta Elair 6040 or similar approved giving 30 lit/sec. output.
Locate light switches and power points in an area between 450mm and 1200m above adjacent finished floor level.
All new lighting points are to be capable of running low energy lighting only.

INTERNAL DRAINAGE

40mm Rev waste to sink unit
75mm deep seal trap to sink unit
Include for rodding access at elbows.



proposed rear elevation nw

WINDOWS

White Rev framed windows with trickle vent systems 8000cm² where serving habitable rooms 4000cm² elsewhere.
Use low E glass with 16mm air gap.
Where glazing in windows is less than 800mm above adjacent finished floor level 1.5m in doors use toughened safety glass to BS6206.



proposed side elevation. SW.

Location Plan scale 1:1250



EXISTING GROUND FLOOR PLAN 1:50m

SCALE BAR 1:50 M
0 0.5 1 2 3 4 5

SCALE BAR 1:100 M
0 0.5 1 2 3 4 5

STEEL BEAMS

Steel Universal Beam sizes to be as structural engineers design sheets.
Box in beams with two layers of 15mm fireline plasterboards with taped tested and sealed joints.

SPACE HEATING / WATER

Extend existing boiler into new covers.





PROPOSED GROUND FLOOR PLAN 1:50m

RADON

Radon Gas Protective measures to be as identified in Report from the British Geological Survey. minimum BASIC Protection be employed
1. extend DPM through to close cavity.
2. DPC trays at GFL to Retain DPM.

FORMING OPENINGS

Where knocking through existing masonry walls to form new openings include for Precast concrete lintels over with end bearings of 150mm minimum 3 courses of blockwork over.
make good reveals in brickwork.

EXTERNAL DRAINAGE

100 back inlet rodddable trapped gullies
White Rev rainwater goods.
Build Mid in 225mm Class B engineering brickwork 600mm x 450mm internally with granite benchmark dished cast iron cover and frame.
100mm dia. Rev below external Pipework laid on chippings bed minimum falls 1in8 minimum 1 in 40.
If new extension is within invert of main foul sewer take floor down below invert.

LANTERN LIGHT

Set new lantern Light by ATLAS or similar set in Roofmasters flashings unit

ROOF VENTILATION

Ventilate roof spaces by warmventing continuous vents to soffits and maintaining a clear 50mm air zone to roof space.

ROOF INSULATION

150mm thick celotex insulation batts to roof space.

ROOF STRAPS

Strap roof walls at 1.8m centres with m.s anchors 30mm x 5mm in cross section. Include for noggins over 3 no joists at gables.

ROOF

Firestone Rubbercover EPDM system on Plyboard decking on flatroofs laid at 1:80 on TJI Joists at 400mm centres 250mm deep. Double up joists around Lantern roof light

CEILINGS

12.5mm foil backed plasterboards with gypsum plaster skim.

FASCIAS

White Rev with white Rev continuous vent soffits.

LINTELS

Catnic Cavity steel lintels and Hanson Dital Lintels over openings with end bearings a minimum 150mm.
DPC trays over vents backed with insulation.



DPC

H-bad horizontal damp proof course.

GROUND FLOOR

50mm Sand and cement screed on 100mm thick site concrete floor slabs on 200mm thick celotex insulation batts on 1200 gauge damp proof membrane on 150mm clean well consolidated hardcore.

FOUNDATION WALLS

Cavity work foundation walls with 100mm dense concrete blockwork inner skin 150mm cavity 100mm dense concrete blockwork outer leaf backfill cavity with lean mix concrete up to DPM.

FOUNDATIONS

750mm wide by 300mm deep 1:3:6 mix traditional strip concrete foundations, depth to suit site conditions min. 900mm.

NOTE

Final ground floor / foundation construction to be determined by inspection of excavations by Approved Inspectors.

PROPOSED SECTION 1:50m

BIODIVERSITY

Supply and fix VIVARA PRO woodstone House Sparrow Nest Box.
Sizes - 160mm deep 290mm high 210mm wide.

NOTES:

All dimensions must be checked on site and not scaled from this drawing.

This plan has been prepared for Planning and /or Building Regulation purposes only.

Some forms of building works may require action by the owners under The Party Wall Act 1996. The adjoining owners are to be informed of the proposals at least one month before commencement of works and their written approvals obtained.

A	23.09.2026	South West elev of annexe added V.J.
	Date	Revisions

© copyright

D. Vivian Jones AssocRICS
Building Design Services
114, Brecon Road,
HIRWAUN,
Rhondda Cynon Taff,
CF44 9NS
Tel. 01685 812069
Mobile 07702 380869
Email: vivjonesdesign@yahoo.co.uk

Client
Mr. David Thomas

Job Title
Proposed Single Storey Extension.

Drawing Title
35, Llewellyn Street,
Glynneath.
NEATH.
Neath Port Talbot.
SA11 5AF.

Scale 1:50 1:100 1:250 1:1250

Date 04.02.2026 Drawn by V.J.

Drg. No. 3067 R Rev.

DS 342

594 x 841mm A1